

APPENDIX G

NOMINATED COUNCIL HOLD POINTS AND COUNCIL WITNESS POINTS

NOMINATED COUNCIL HOLD POINTS AND COUNCIL WITNESS POINTS

STAGE	REQUIREMENT	TIMING	TYPE
PRELIMINARIES			
Environmental Protection	Protection measures in place	Prior to other works commencing	CHP
Traffic Management	Vehicle/Pedestrian guidance in place	Prior to works commencing	CHP
Site Safety	Safety measures in place	Prior to works commencing	CWP
Pre-commencement	Pre-commencement Meeting	Prior to works commencing	CHP
BULK EARTHWORKS			
Grubbing and Clearing	Tree protection fencing	After installation	CHP
	Removal of native trees	Prior to removal	CHP
Stripping and/or base preparation	Placing filling on stripped areas	Prior to placing filling	CHP
Boxing	Road formation	Prior to covering	CHP
Subgrade Improvement	Treatment of Soft Areas	Prior to backfilling	CHP
Capping Layer	Proof rolling, test results, levels and shape	Prior to placement of pavement	CHP
Subgrade	Proof rolling, compaction test results, levels and shape	Prior to placement of pavement	CHP
Formation	Grading and levels	Prior to topsoiling	CHP
Nature Strips	Grading and levels	Prior to topsoiling	CHP
DRAINAGE			
Drainage pipes	Foundation Bed	Prior to laying of pipes	CWP
	Levels, alignment, jointing and haunching	Prior to backfilling	CHP
	Backfill	After Backfilling	CWP
Pits and Structures	Formwork, bedding and reinforcement	Prior to pouring concrete	CHP
	Backfilling	Prior to pavement	CHP
Agricultural Drains	Levels and alignment	Prior to Backfilling	CHP
	Electricity Pole installation	During installation	CWP
House Drains	Levels and alignment	Prior to backfilling	CHP
	Pipe connection at outlet	Prior to backfilling	CHP
Culverts	Levels and alignment	Prior to placement	CHP
SEWER			
Sewer trench	Compaction Test Results	After Backfilling	CWP
CONDUITS			
Road crossings	Levels and alignment	Prior to Backfilling	CHP
Footpath/Nature Strip	Levels and alignment	Prior to Backfilling	CHP



CONCRETE			
Concrete curing	Curing method and application	During work	CWP
Kerb and Channel	Proof roll bedding	Prior to placement of kerb and channel	CHP
	Alignment	Prior to pouring concrete	CHP
	Backing up	Prior to placement of pavement	CHP
Footpath	Bedding, alignment, reinforcement, jointing	Prior to pouring concrete	CHP
Vehicle Crossings	Bedding, levels, reinforcement and dowels	Prior to pouring concrete	CHP
Thresholds and Islands	Bedding, levels, reinforcement and dowels.	Prior to pouring concrete	CHP
PAVEMENT			
Base Course	Proof roll and compaction	Prior to placement of intermediate course	CHP
Intermediate Course	Proof roll each layer	Prior to placement of subsequent layer	CWP
Top Course	Proof roll and compaction	Prior to placement of asphalt/seal	CHP
Seal	Sweeping, paper protection	Prior to placement of seal	CWP
Asphalt	Depth, spread rate, temperature, compaction	During Works	CWP
Linemarking	Spotting out	Prior to linemarking	CHP
Concrete Pavements	Formwork, reinforcement and jointing	Prior to pouring	CHP
ROCK BEACHING			
Bedding	Level and compaction	Prior to placing rock beaching	CHP
PRACTICAL COMPLETION			
Quality, Access and Public Safety	Practical completion Inspection	Prior to consenting to commencement of the defects liability period	CHP
END OF DEFECTS LIABILITY			
Quality, Access and Public Safety	End of Defects Liability Inspection	Prior to consenting to the end of the defects liability period	CHP