

Shepparton North-East Growth Corridor Development

Addendum to

Traffic Impact Assessment Report

Client:

Greater Shepparton City Council

Project 170769

Addendum Report B, Rev 2: 13/07/2018

1st Floor 132 Upper Heidelberg Road Ivanhoe Vic 3079 PO Box 417 Ivanhoe Vic 3079 Ph: (03) 9490 5900 Fax: (03) 9490 5910 www.trafficworks.com.au



DOCUMENT CONTROL RECORD

Document prepared by:

Trafficworks Pty Ltd ABN 59 125 488 977

1st Floor 132 Upper Heidelberg Rd, Ivanhoe, Vic 3079

PO Box 417, Ivanhoe, Vic 3079

Ph (03) 9490 5900

Fax (03) 9490 5910

www.trafficworks.com.au

DISCLAIMER

The information contained in this document is intended to be received, used and relied upon by the named addressee or client only for the purpose for which it has been prepared. Trafficworks Pty Ltd does not warrant the accuracy or relevance of the information, including by implication, contained in this document if it is used or relied upon by any person other than the named addressee or client. Copying, reproduction including by electronic means, unauthorised use or disclosure of this document is prohibited except with the express written authorisation of Trafficworks Pty Ltd.

Document Co	ontrol	OTRAFFICWORKS							
Report Title			Shepparton North East Growth Corridor Development Addendum B to Traffic Impact Assessment Report						
Project Numb	per	170769							
Client		Greater Shepparton C	ity Council						
Client Contac	cts	Michael MacDonagh							
Rev	Date Issued	Revision Details / Status	Prepared by	Reviewed by					
Draft	30/06/2018	For review by client	Bob Citroën						
Draft #2	5/07/2018	For review by client	Bob Citroën						
Final	11/07/2018	For issue to client	Bob Citroën	Kate Kennedy					
Final Rev 1	12/07/2018	For issue to client	Bob Citroën						
Final Rev 2	13/07/2018	For issue to client	Bob Citroën						

170769: Shepparton NEGC TIAR Addendum B



TABLE OF CONTENTS

1	PREAMBLE	ii
	1.1 Background	ii
	1.2 Executive Summary	iii
	1.3 References	iv
2	BASIS FOR ASSESSMENTS	1
	2.1 Land parcels	1
	2.2 Traffic generation and distribution	2
	2.3 SIDRA Assessments	3
3	ASSESSMENTS	5
	3.1 Access options	5
	3.2 Connector road profiles	7
	3.3 Cross sections	9
	3.4 Functional design	9
	3.5 Costings	. 10
	3.6 Additional matters	. 11
6	CONCLUSIONS AND RECOMMENDATIONS	. 13
Α	TTACHMENT A -INTERNAL ROAD CROSS-SECTIONS	. 14
Α	TTACHMENT B - SIDRA SUMMARIES	.21
Α	TTACHMENT C – URBAN ROAD STANDARDS	.27
Α	TTACHMENT D - TRAFFIC ESTIMATES	. 28
Α¯	TTACHMENT E - POST-EXHIBITION CROSS-SECTIONS	.30
	TTACHMENT F - ROAD LENGTH COST ESTIMATES	



1 PREAMBLE

1.1 Background

In 2014 Trafficworks Pty Ltd was engaged by Greater Shepparton City Council to prepare a comprehensive Traffic Impact Assessment Report (TIAR) for the Shepparton North-East Growth Corridor (refer final report dated 15/09/2014).

Further development of the growth corridor proposals since completion of the above report has included referral and review of the proposed structure plan for the precinct to the Victorian Planning Authority (VPA) and the exhibition of Amendment C118 that provides the framework to develop the land in accordance with the Shepparton North East Precinct Structure Plan (NEPSP).

The Shepparton North-East Growth Corridor covers an area of approximately 170ha that is bounded by Verney Road to the west, Ford Road to the north and the Shepparton Alternative Route (locally known as Grahamvale Road) to the east.

Verney Road along the precinct's western boundary is included in a Road Zone (Category 2) in the Greater Shepparton Planning Scheme and is managed by Council. Verney Road is designated as a trunk collector road in the local road network. Council has recently upgraded Verney Road to comprise a three-lane divided cross section (one lane in each direction separated by a central painted median providing sheltered right-turn lanes at all significant intersections) and incorporating on-road bicycle lanes. It is currently subject to a 60km/h speed limit along the precinct frontage, with a time-based 40km/h school zone along the frontage of Shepparton Christian College. As well as the on-road cycle lanes, an off-road shared path has been constructed to the west of the reservation from Elm Terrace in the south to Ford Road in the north.

Council is in the process of upgrading the Balaclava Road / Hawdon Street / New Dookie Road / Verney Road intersection from a roundabout to a signalised intersection. Works on this project are planned to be undertaken over the 2018/19 and 2019/20 financial years.

Ford Road that forms part of the northern boundary to the PSP is included in the Road Zone (Category 2). This is also designated as a trunk collector road in the local road network and it is managed by Council. It currently has a two-lane two-way cross-section within a 20m road reservation width. Ford Road operates under a 60km/h speed limit.

Council, in collaboration with VicRoads, is investigating the possibility of upgrading Ford Road (between the Goulburn Valley Highway and Grahamvale Road), and its extension east of the highway along Wanganui Road, to serve as a direct connection and critical link between Stage 1 of the Goulburn Valley Freeway Bypass of Shepparton and the Shepparton Alternative Route. Council, in association with VicRoads, prepared the *Draft Wanganui Road and Ford Road, Shepparton: Feasibility Study Design Report 2018*. The Report explores the options and constraints to upgrading Ford and Wanganui Roads to serve as an east-west connecting link. At the Ordinary Council Meeting held on 20 February 2018, Council resolved to endorse the Draft Report and to release it for public comment for a period of eight weeks, commencing on 26 February 2018 and concluding on 23 April 2018.

170769: Shepparton NEGC TIAR Addendum B



Greater Shepparton City Council and the VPA have engaged Trafficworks to prepare an Addendum Report to the 2014 TIAR for the North East Growth Corridor that investigates the following aspects of the PSP:

a. Intersections

- i. The impact of deletion or change to left-in/left-out operation for the intersection at Access B onto Ford Road
- ii. The impact of deletion or change to left-in/left-out operation for the intersection at Access C onto Grahamvale Road
- iii. The impact on the road network of the above changes at both intersections
- iv. The best solution for access to the NEPSP, including whether the traffic signals proposed for Access A can be deleted and the traffic signals for Access D can be replaced with a roundabout
- v. Comment on the intersection layout for Access A (lane arrangement for east approach) and Access D (realignment of east approach into No 145 parcel 13).

b. Connector Road Widenings

- i. Determine the minimum access road standards at Accesses A, C and D if abutting land holdings were developed in isolation
- ii. Assess the ultimate cross sections and lengths for these access roads to determine the differential to be funded from the DCP.

c. Cross Sections

i. Review the post-exhibition cross sections.

d. Functional Drawings

- i. Prepare concept plans for all proposed road lengths
- ii. Prepare functional plans for the minimum and ultimate standards under item b).

e. Costings

- i. Comment on probable costs for each intersection.
- ii. Comment on probable costs for connector road options in item b).

1.2 Executive Summary

The principal conclusions drawn from the investigations undertaken as part of this addendum to the 2014 TIAR are that:

- Internal traffic diversions resulting from closure of Access B can be accommodated within the network and the proposed intersection treatment at Access A.
- Partial (left-in/left-out) control at Access B is expected to result in adverse safety outcomes and is not recommended.

170769: Shepparton NEGC TIAR Addendum B



- Reassignment of traffic from a closure of Access C is expected to result in serious congestion, delays and queuing issues at Access D, with downstream negative network implications further south along Verney Road. The planning wisdom of denying an easterly access into the precinct is also questioned and closure of Access C is not supported.
- Partial (left-in/left-out) control at Access C is also expected to result in adverse safety outcomes and is not recommended. However, the replacement of Accesses B and C with a combined access, by way of an additional leg to the proposed roundabout at the intersection of Ford Road and Grahamvale Road, is an option that should be further investigated.
- The amended post-exhibition road profiles result in closer alignment of cross-sections with those recommended in the IDM. However, consideration should be given to further adjustments to include an off-road shared path in the cross-section for Road-04 and retaining the IDM cross-section (with two lanes in each direction) for Road-02 if closure of Access C proceeds.

1.3 References

Reports and technical references used in the preparation of this report include the following:

- Shepparton North East, Precinct Structure Plan, prepared by the Victorian Planning Authority and dated February 2018
- Shepparton North East, Development Contributions Plan, prepared by the Victorian Planning Authority and dated February 2018
- Greater Shepparton Planning Scheme Amendment C118, Explanatory Report
- Ford and Wanganui Roads Investigation Study on Greater Shepparton City Council website
- Wanganui Road/Ford Road, Shepparton Road and Intersection Upgrade Functional Design, Road Safety Audit Report, conducted by RSA and dated 27/11/2017
- Ford and Wanganui Road Masterplan, prepared by McGregor + Coxall, Sheets LD-SK-P01 to P04
- Shepparton North East Growth Corridor Development, Traffic Impact Assessment Report, prepared by Trafficworks Pty Ltd dated 15 September 2014
- Shepparton North East Growth Corridor Development, Traffic Impact Assessment Report Addendum A, prepared by Trafficworks Pty Ltd dated 11 January 2017
- Local Government Infrastructure Design Association's *Infrastructure Design Manual*, Version 5.10, released 11 Jan 2018
- Shepparton North East Growth Corridor, Structure Plan, Traffic Engineering Assessment, by TraffixGroup Pty Ltd dated 7 March 2011.

170769: Shepparton NEGC TIAR Addendum B



2 **BASIS FOR ASSESSMENTS**

2.1 Land parcels

In order to draw meaningful comparisons with the 2014 TIAR, the land splits as described in the Ownership Plan prepared by Reeds Consulting (refer Figure 1) have been used in the manipulation of the traffic generation model in Attachment D to this report. Cross references between land parcels in Plan 3 of the PSP (on page 10 of the PSP) and the ownership areas as defined in the Reeds plan and the traffic generation model are detailed in Table 1.

MONDOUS MONDOUS SFETKOPOULOS MONDOUS DRAINAGE CHANNEL CHRISTIAN SCHOOL BENNETT MONDOUS 10 SALI DAMIEN 5 DAMIEN DRAINAGE CHANNEL OWNERSHIP PLAN REEDS RNEY AND FORD ROADS, SHEPPARTON

Figure 1: Ownership Plan (Source: Reeds Consulting "Ownership Plan Version A"). Plan includes access point notation.



Table 1: Cross references between land parcels in the PSP and Reeds Ownership Plan

PSP Parcel Number	Ownership Area Number
1	6 (Mondous)
2	11 (Drainage channel)
3	1 (Mondous)
4	7 (Mondous)
6	2 (Sfetkopoulos)
12	8 (Christian School)
13	9 (Bennett)
14	3 (Mondous)
15	Grahamvale School
16	Not identified
17	10 (Sali)
25 & 26	4 & 5 (Damien)

2.2 Traffic generation and distribution

For consistency with the previous TIA reports, the following parameters have been adopted in this report for establishing traffic generation from within the precinct:

- Lot yield = 10 dwellings/hectare applied to gross areas. This is consistent with the PSP but introduces a 10% reduction on the previous TIAR estimates based on 11 dwellings/hectare
- Generation rate = 8 trips/dwelling/day, with 10% occurring in the AM and PM peaks
- Traffic generation by the neighbourhood centre has assumed that 90% will be generated within the precinct and 10% externally
- The 2014 assessment was conducted on the basis of an 80% exiting/20% entering directional split in the AM peak and a 70% entering/30% exiting directional split in the PM peak for residential traffic
- The distribution of residential traffic outlined in the 2011 TraffixGroup report and used as a basis for traffic distribution in the 2014 TIAR, as depicted in Figure 2.

In order to estimate changes in traffic patterns upon the closure of Accesses B and C, the following reassignments have been undertaken in the traffic model:

- From Access B: 8% (3% to north + 5% to east) reassigned to Access A all directed north
- From Access C: 2% reassigned to Access A and directed north

25% (20% south +5% east) reassigned to Access D and directed south 2% reassigned to Access D and directed west (along Pine Road)

170769: Shepparton NEGC TIAR Addendum B






Figure 2: Adopted traffic distribution (Source: Figure 8 from TraffixGroup report dated 7/3/2011)

2.3 SIDRA Assessments

Assessments of intersection operation at Accesses A, B, C and D for the 2014 TIAR concluded that the following controls be implemented:

- Access A: Operation was considered satisfactory under Give Way control with Type CHR and Type AUL turn lanes provided in Verney Road. It is noted that this assessment only considered the impact of the PSP and did not include Ryeland Drive traffic. Council's preference was for signalisation.
- Access B: Give Way control was considered satisfactory onto Ford Road with Type AUL left turn lane from the east.
- Access C: The heavy demand for west to/from south turn movements made Give Way control unsuitable, a roundabout marginal (requiring two lane operation) but operation expected to be satisfactory under traffic signal control.
- Access D: Total traffic volumes made Give Way control unsuitable. The analysis confirmed satisfactory operation under the signalised intersection proposed by Council. A roundabout option was not assessed, given the constraints imposed on the footprint for such a treatment by adjacent existing development.

An explanation of the intersection operating characteristics is shown in Table 2. Note that good or better operating conditions relates to an intersection operation below the practical capacity.



Table 2: Definitions of intersection operation characteristics

Degi	ree of Saturation	(DOS)	
Sign control	Roundabout	Traffic Signals	Operation
Less than 0.60	Less than 0.60	Less than 0.60	Excellent operating conditions, minimal delays
0.60 - 0.70	0.60 - 0.70	0.60 - 0.70	Very good operating conditions, minimal delays
0.70 - 0.80	0.70 - 0.85	0.70 - 0.90	Good operating conditions, delays and queuing increasing
0.80 - 0.90	0.85 - 0.95	0.9 - 0.95	Acceptable operating conditions, delays and queues growing. Any interruption to flow such as minor incidents causes increasing delays
0.90 - 1.00	0.95 - 1.00	0.95 - 1.00	Poor operating conditions, flows starting to break down and queues and delays increase rapidly.
Above 1.00	Above 1.00	Above 1.00	Very poor operating conditions with queues and delays increasing rapidly. Once queues develop it takes a significant time for queues to dissipate resulting in long delays to traffic movements.



3 ASSESSMENTS

3.1 Access options

i) Access B onto Ford Road

Closure of this intersection would result in the reassignment of all traffic from Access B to Access A. With reference to the traffic distribution plan in Figure 2, this would comprise 5% of internally generated traffic to/from destinations to the east and 3% of internally generated traffic to/from the north. As such, all this traffic at Access A would depart to and enter from the north.

Under the redistribution caused by closures of Accesses B and C, a total of 40% of internally generated traffic will use Access A. The 8% (5% + 3%) component of internal traffic redirected from Access B will represent 1/5 (8/40) of total traffic at Access A. Under the impact of this added traffic and with the addition of Ryeland Drive traffic to this intersection, the SIDRA assessment has indicated that this intersection will operate satisfactorily under Give Way control with a Degree of Saturation (DoS) of 0.834, average delays of 42 seconds and 95% queue lengths of 46m in the east approach during the AM peak (refer Figure B1 in Attachment B). Operation during the PM peak is also expected to be satisfactory under Give Way control (refer Figure B2 in Attachment B) and operation of the intersection under signalised control is excellent in both AM and PM peak periods.

Conversion of Access B to left-in/left-out only movements is expected to result in no change in travel patterns from those in the PSP. As movements are expected to be almost exclusively to/from the east the mooted restriction will:

- Have no impact on traffic entering the PSP from the east
- Result in exiting traffic exiting onto Ford Road in a westerly direction and conducting a U turn at the earliest opportunity at nearby driveways or within the Matilda Drive intersection. These U turn manoeuvres are considered hazardous and present a strong case against implementation of partial control at this access.

The impact of the partial control at Access B is not explored further.

In summary, traffic redistribution resulting from closure of Access B can be accommodated without change at Access A. Partial closure of Access B is not recommended for safety reasons.

ii) Access C onto Grahamvale Road

Closure of this intersection would result in the reassignment of all traffic from Access C to Accesses A and D. With reference to the traffic distribution plan in Figure 2, this would comprise 2% of internally generated traffic reassigned to Access A to/from destinations to the north, and a total of 27% of internally generated traffic reassigned to Access D, distributed 2% to/from the west and 25% to/from the south.

This represents an almost 50% increase in traffic at Access D. SIDRA analysis indicates that the intersection will operate well above practical capacity during the AM and PM peaks, exhibiting serious congestion, delays of several minutes and queues hundreds of metres long in the north,

170769: Shepparton NEGC TIAR Addendum B



east and south approaches. The intersection will require significant modification to obtain acceptable operating conditions (refer Figures B3 and B4 in Attachment B).

Conversion of Access C to left-in/left-out only movements is expected to favour the entry movement from the south that represents 27% of the 29% of internally generated traffic at this access. However, control over the heavy demand for southbound departure movements could not be safely accommodated without a roundabout at the Ford Road/Grahamvale Road intersection in the first instance.

Even if it is assumed that a roundabout is provided at Ford Road/Grahamvale Road, it is expected that it will require the construction of a median for the full distance between Access C and this roundabout to prevent hazardous U turn movements being executed by departing southbound vehicles. Partial (left-in/left-out) control at Access C is not recommended.

In summary, closure of Access C will result in substantial increases in traffic at Access D to the extent that the proposed signals at this intersection will operate beyond practical capacity at peak times. Partial control at Access C will require the completion of the proposed roundabout at the Ford Road/Grahamvale Road intersection and the likely need to install a median between this roundabout and Access C for it to operate safely.

iii) Network impacts

As noted above, the anticipated traffic redistribution resulting from closure of Accesses B and C can be accommodated at Access A with Give Way control or under the signals control proposed at this intersection. The small increase in traffic volumes in Verney Road to the north and through the Ford Road intersection is also expected to be catered for without difficulty, whether this intersection is ultimately configured as a roundabout or signals.

However, the 50% increase in traffic at Access D is expected to cause significant congestion, queuing and delays at the intersection.

In addition, the downstream impact of this additional traffic on the Verney Road leg of the New Dookie Road/Balaclava Road/Hawdon Street intersection to the south of Access D is significant and is expected to seriously reduce the design life of the new signals proposed for this intersection.

iv) Alternative access configurations

Access A: This intersection is expected to operate satisfactorily under Give Way control. However, as noted earlier in this report, Greater Shepparton City Council has expressed a preference for signalisation of this intersection. Development of the community hub at the northeast corner of the intersection is expected to attract considerable pedestrian traffic along Ryeland Drive from the residential areas to the west of Verney Road. In addition, pedestrian traffic generated by the Christian School to the south of Access A (PSP parcel 12) has required the recent installation of a flagged school crossing across Verney Road at the school frontage. It is expected that continued growth of this school will require the upgrading of the crossing facility in the near future and the installation of traffic signals at Access A would also service this need. Signalisation of Access A is considered desirable for operational as well as safety reasons.

170769: Shepparton NEGC TIAR Addendum B



It is noted that, with signalisation, the sight line issues raised during the exhibition period, in relation to the multiple stand-up lanes in the east approach, no longer play a part in the safe operation of the intersection.

Access D: Development of layout options at the cross-intersection with Verney Road and Pine Road at Access D is constrained by the existing development at No 125 Verney Road (PSP parcel 16). This was nominated as a control during the development of the 2014 TIAR, which results in an off-set between the east and west legs. The offset can be accommodated in the layout for signalisation of the intersection (refer DCP page 47) but would not permit the development of a suitable and functional roundabout layout without incursion into No 125.

Accesses B & C: Closure of Access B and, in particular, Access C makes it difficult for Access D and Verney Road to accommodate the resultant additional reassigned traffic demand. From an overall accessibility perspective it is also considered undesirable for all access to the precinct to be westerly oriented, with no connection to the abutting road network to the east.

In response to these issues, the option of a connection to the proposed roundabout at the intersection of Ford Road with Grahamvale Road has been mooted, by way of an additional leg to replace both Accesses B and C. A concept layout for a modified roundabout has been investigated by VicRoads and appears to offer a viable alternative to replace the two separate access points. It is noted that such a change of access would also involve significant modifications to the internal road layout for the northeast quadrant of the PSP.

In summary Closure of Access C is expected to significantly reduce the design life of the proposed signalisation of the intersection of Verney Road with New Dookie Road/Balaclava Road, and is considered an undesirable constraint on easterly access to the precinct. It is recommended that the option of providing access to the roundabout at Ford Road/Grahamvale Road be further investigated.

3.2 Connector road profiles

Road-01: This road is located along the boundaries of PSP parcels 1 and 4 (Mondous lots 6 and 7 on the Reeds plan). If it is assumed both parcels are fully developed and yield a total of 268 lots (26.8ha @ 10 lots/ha) plus the commercial hub, traffic generation can be expected to reach 2,300vpd at Access A (including 10% contribution from the shops to/from external destinations). The IDM indicates this to be just below the threshold of the traffic range for a Connector Street, requiring only an Access Street profile (refer copy of IDM Table 2 in Attachment C). It is noted that inclusion of the currently vacant land at the rear of the Christian College property – the eastern portion of parcel 12 (or lot 8) - would increase traffic generation at Access A to 2,700vpd or above the maximum for an Access Street.

Traffic will progressively decrease along this road to the east and, although it will need to accommodate the 90% traffic contribution from the shops that is internally generated, it is considered that an Access Street designation can be applied to the full length of Road-01 through parcels 1 and 4 if undertaken as stand-alone developments. With the eastern portion of parcel 12 included, the western end should be upgraded to Connector Level 1, reducing to Access Street at the eastern boundary of the open space adjacent to the community hub for the remaining distance to the east.

170769: Shepparton NEGC TIAR Addendum B




Ultimate traffic volumes at Access A, with Accesses B and C closed and based on a yield of 10 lots/ha, indicate traffic volumes just above the 6,000vpd threshold for a Trunk Collector Road and a need to implement this road profile for the first 25% of its length through parcels 1 and 4 (i.e. from Verney Road to east of the community hub). From this point a Connector Street Level 1 profile would need to be maintained along Road-01 to its intersection with Road-03/Road-04.

Road-02: This road connects with Verney Road at the boundaries of PSP parcels 13, 16 and 17 (Bennett lot 9 and Sali lot 10, with parcel 16 not identified on the Reeds plan). If it is assumed parcels 13 and 17 are fully developed and yield a total of 305 lots (30.5ha @ 10 lots/ha), traffic generation can be expected to reach 3,050vpd at Access D. The IDM indicates this to be well within the traffic range requiring a Connector Street Level 1. Assuming traffic will exhibit a linear decrease along this road to the east, volumes will drop below the Level 1 Connector Street threshold at about one fifth of the distance through parcel 13 and its designation can be reduced to Access Street at approximately 150m from Verney Road if parcels 13 and 17 are undertaken as stand-alone developments.

Ultimate traffic volumes with Access C closed indicate traffic levels in the order of 12,500vpd, which exceed Trunk Collector Road designation. These high traffic volumes progressively reduce along Road-02, to fall within the range for a Trunk Collector at approximately 50m east of Verney Road, and would be expected to continue within the range of Trunk Collector for the remaining length of this road.

Road-03: This road is shown in the PSP to enter parcel 6 (Sfetkopoulos lot 2 on the Reeds plan) from Grahamvale Road immediately north of parcel 7. If it is assumed parcel 6 is fully developed and yields a total of 250 lots (25.04ha @ 10 lots/ha), traffic generation can be expected to reach 2,500vpd at Access C. The IDM indicates this to be at the threshold between Access Street and Connector Street Level 1. As traffic will progressively decrease along this road, it is considered reasonable for its full length to be designated as Access Street if parcel 6 is undertaken as a stand-alone development.

Ultimate traffic levels along Road-03, assuming retention of Access C onto Grahamvale Road and a yield of 10 lots/ha (representing a 10% reduction on the 2014 estimates based on 11 lots/ha), are estimated to be in the order of 5,300vpd and require upgrading of this road to Connector Road Level 1 from Grahamvale Road to its junction with Road-01 and Road-04.



170769: Shepparton NEGC TIAR Addendum B



3.3 Cross sections

Section 4.2 (Appendix B) to the PSP provides a series of street cross-sections, generally in accordance with Table 2 of the Infrastructure Design Manuel (IDM) reproduced in Figure C1 of Attachment C. These cross-sections were modified following exhibition with the updates provided in Attachment E to this report.

The updated cross-sections for Local Access Street (16.0m), Park and Retardation Basin Interface Street (16.0m) and Reserve and School Interface Street with shared path (17.0m) all provide a 7.3m carriageway width (consistent with Access Street in the IDM) and varying verge width configurations. Implementation of the strategy in Plan 5 of the PSP would result in the selection of the appropriate cross-sections that include shared path facilities along key cycling routes.

The Key Local Access Street (18.0m) has been superseded by specific Interface Streets (18.0m) for the Ford Road and Verney Road frontages. These also contain 7.3m wide carriageways and varying verge width configurations. However, Road-04 (between Road-01/Road-03 and Ford Road, which previously had Key Local Access Street status) will need to be designated Interface Street (17.0m) to incorporate an off-road shared path.

The modified cross-section for Connector Street Level 1 (24.0m) is consistent with the IDM Connector Street Level 1, and now provides an 11.6m wide carriageway with shared paths along both sides of the road. This cross-section is supported where applied to the appropriate traffic volume range.

The modified cross-section for Connector Street Level 2 (30.0m) or Trunk Collector has reduced the cross-section nominated in the IDM by limiting traffic to a single lane in each direction. This cross-section is expected to result in congestion where required to operate under the higher traffic volumes expected along Road-02 with closure of Access C. However, if Access C is retained, traffic volumes along Road-02 would reduce to an extent that the proposed modified cross-section for Connector Street Level 2 (30.0m) is expected to operate satisfactorily.

In summary, consideration should be given to amending the post-exhibition road profiles to include an off-road shared path in the cross-section for Road-O4 and retaining the IDM cross-section (with two lanes in each direction) for Road-O2 if Access C is closed.

3.4 Functional design

The functional layout plans in Section 6.2.1 of the DCP should be updated to provide the following profiles for the key connector roads through the PSP, as outlined in Figures 3A and 3B:

Road-01: Beyond the limits of the Trunk Collector Road for the first 100m from the signals at Verney Road to east of the community hub, Section 3.2 above indicates an ultimate requirement for a Connector Level 1 (24m) profile for this road to its junction with Road-03/Road-04. This configuration is outlined in the functional plan on page 37 of the DCP, but with the width reduced to 24.0m (refer to Figure A1 of Attachment A) and is supported.

170769: Shepparton NEGC TIAR Addendum B



If parcels 1 and 4 are undertaken as a standalone development then the full length of this road can be maintained as an Access Street (refer to Figure A2 of Attachment A).

Road-02: Ultimate traffic volumes indicate a need for the full length of this road to be configured as a Trunk Collector Road as detailed in the functional plan on page 42 of the DCP but with the width reduced to 30.0m (refer to Figure A3 of Attachment A). It is noted that, if Access C is closed, the western 50m of the road is expected to experience traffic volumes in excess of the range for a Trunk Collector as set out in the IDM. It is considered that the IDM cross-section (34.0m) should be the minimum standard adopted for this road if closure of Access C proceeds to better accommodate mid-block traffic volumes. However, significant capacity issues would still exist at the intersection of Road-02 with Verney Road.

If parcels 13 and 17 are undertaken as a standalone development then this road can be maintained as an Access Street, with the first 150m east of Verney Road configured as a Connector Road Level 1 (refer to Figure A4 of Attachment A).

Road-03: Ultimate traffic volumes indicate a need for the full length of this road to be configured as a Connector Road Level 1 as detailed in the functional plan on page 39 of the DCP but with the width reduced to 24.0m (refer to Figure A5 of Attachment A).

If parcel 6 is undertaken as a standalone development then the full length of this road can be maintained as an Access Street (refer to Figure A6 of Attachment A).

Road-04: In addition to the above, traffic volumes in Road-04, at both stand-alone and integrated stages, indicate a need for its full length to be configured as an Interface Street (Section 4 - 18m) so as to provide a shared path along this designated cycling route.

3.5 Costings

3.5.1 Road Lengths

Order-of-cost estimates have been prepared for Road-01, Road-02 and Road-03, based on the modified cross-sections discussed above and using the unit rates from Section 6.2.1 of the DCP. Individual cost estimates for each road option, i.e. stand-alone development (Interim 1), integrated development as assessed in this report (Interim 2) are shown in Attachment F.

In addition, cost estimates have been reviewed to reflect the post-exhibition amended PSP cross-sections for each road (refer Attachment E). These are noted as Connector Street Level 1, 24m (Ultimate 1) and Trunk Collector, 30m (Ultimate 2) in each case. Revised estimates for these options are also shown in Attachment F.

The costs associated with all four options for each road are summarised in Table 3.

It should be noted that, in order to provide valid comparisons with costings shown in the DCP, the lengths of each road treatment considered in these cost estimates are close approximations of the road lengths described in Plan 5 of the PSP and do not necessarily extend for the full length of the subject parcels.

170769: Shepparton NEGC TIAR Addendum B Final Rev 2: 13/07/2018

10



Table 3: Cost estimates for road length options

Road Length	Treatment description	Total cost
Road-01 Interim 1	Access Street (16m) full length	\$ 924,449
Road-01 Interim 2	Connector Street L1 (24m) with 100m Trunk Collector terminal	\$1,130,165
Road-01 Ultimate 1	Connector Street L1 (24m as per PSP) no roundabout	\$1,105,902
Road-01 Ultimate 2	Trunk Collector full length (30m as per PSP) & roundabout	\$1,691,129
Road-02 Interim 1	Access Street (16m) with 150m Connector Level 1 terminal	\$1,320,959
Road-02 Interim 2	Trunk Collector full length (30m)	\$1,896,026
Road-02 Ultimate 1	Connector Street L1 (24m as per PSP) no roundabout	\$1,700,245
Road-02 Ultimate 2	Trunk Collector (30m as per PSP) full length & roundabout	\$1,930,724
Road-03 Interim 1	Access Street (16m) full length	\$ 924,449
Road-03 Interim 2	Connector Street L1 (24m) full length	\$1,108,564
Road-03 Ultimate 1	Connector Street L1 (24m as per PSP) no roundabout	\$1,105,902
Road-03 Ultimate 2	Trunk Collector full length (30m as per PSP) & roundabout	\$1,691,129

3.5.2 Intersections

There has been no substantial change to the proposed intersection treatments as described in the DCP. The cost estimate for the signalisation of the intersection of Verney Road with Road-02 and Pine Road was reviewed as representing the most complex of the proposed external connections. The estimate of \$1,124,336 provided in the DCP was confirmed as being realistic, albeit slightly conservative. On the basis of this review, the remaining intersection cost estimates in the DCP are supported.

3.6 Additional matters

Submissions made during the exhibition process included discussion on the following four matters, on which Greater Shepparton City have requested Trafficworks to provide comment.

- 1) Change of control at Access A from traffic signals to a small roundabout. As noted in Section 3.1(iv), although this intersection is expected to operate satisfactorily under Give Way control, to provide a safe crossing of Verney Road for the anticipated pedestrian movements between the community hub at the northeast corner of this intersection and residential areas to the west, and to cater for an impending need to upgrade the flagged the school crossing to the south of the intersection, Greater Shepparton City's preference for the signalisation of this intersection is supported.
 - Conversion of control to a roundabout will not assist in addressing either of the above pedestrian needs.
- 2) Realignment of the connection of Road-O2 to form a conventional cross intersection with Pine Road and Verney Road (Access D). As noted in Section 3.1(iv), the alignment shown in the PSP is necessary to avoid impact on the existing residence at No 125 Verney Road. A square intersection layout would require the acquisition of No 125 and converting part

170769: Shepparton NEGC TIAR Addendum B



of this land into road. The installation of a roundabout would involve an even greater incursion into No 125.

An option to realign Road-02 to the south of the open space (OS-02) and adjacent retardation basin (RB-02) is expected to have no operational impacts on traffic, either along Road-02 or at the Verney Road intersection, but it would have the benefit of the location of Road-02 being shared between Parcels 13 and 17. Such a realignment would result in slightly better coverage of the bus catchment in the southeast quadrant of the PSP from the consequent relocated bus stop. However, it would require a shift of the key local access street between Road-01 and Road-02 to maintain north-south connectivity clear of the reserve.

3) Sight lines from Road-01 at Access A. The configuration of the multiple east approach lanes to offer optimum visibility along Verney Road for drivers exiting Road-01 is a matter that would need to be addressed in detailed design if a simple Give Way controlled intersection were to be installed. As noted in Section 3.1(iv), with a preference for signalisation of this site, the sight line issue does not play a part in the safe operation of a signalised intersection.

12



6 CONCLUSIONS AND RECOMMENDATIONS

The principal conclusions drawn from the investigations undertaken as part of this addendum to the 2014 TIAR are that:

- Internal traffic diversions resulting from closure of Access B can be accommodated within the network and the proposed intersection treatment at Access A.
- Partial (left-in/left-out) control at Access B is expected to result in adverse safety outcomes and is not recommended.
- Reassignment of traffic from a closure of Access C is expected to result in serious congestion, delays and queuing issues at Access D, with downstream negative network implications further south along Verney Road. The planning wisdom of denying an easterly access into the precinct is also questioned, and closure of Access C is not supported.
- Partial (left-in/left-out) control at Access C is also expected to result in adverse safety outcomes and is not recommended. However, the replacement of Accesses B and C with a combined access, by way of an additional leg to the proposed roundabout at the intersection of Ford Road and Grahamvale Road, is an option that should be further investigated.
- The amended post-exhibition road profiles result in closer alignment of cross-sections with the IDM. However, consideration should be given to further adjustments to include an off-road shared path in the cross-section for Road-04 and retaining the IDM cross-section (with two lanes in each direction) for Road-02 if closure of Access C proceeds.


170769: Shepparton NEGC TIAR Addendum B




ATTACHMENT A -INTERNAL ROAD CROSS-SECTIONS

170769: Shepparton NEGC TIAR Addendum B Final Rev 2: 13/07/2018































ATTACHMENT B - SIDRA SUMMARIES

Figure B1: LANE SUMMARY

Site: 101v [Verney Road / Ryeland Drive / Access A - AM peak]

New Site

Site Category: (None) Giveway / Yield (Two-Way)

Lane Use a	nd Perfori	manc	е										
	Demand F	Flows HV	Сар.	Deg. Satn	Lane Util.	Average Delay	Level of Service	95% Back Veh	of Queue Dist	Lane Config	Lane Length		
	veh/h	%	veh/h	v/c	%	sec			m		m	%	%
South: Verne	y Road												
Lane 1	8	1.0	1844	0.005	100	6.4	LOS A	0.0	0.0	Short	55	0.0	NA
Lane 2	213	3.0	1897	0.112	100	0.0	LOS A	0.0	0.0	Full	500	0.0	0.0
Lane 3	80	1.0	976	0.082	100	8.0	LOS A	0.3	2.3	Short	45	0.0	NA
Approach	301	2.4		0.112		2.3	NA	0.3	2.3				
East: Access	Α												
Lane 1	318	1.0	956	0.333	100	6.6	LOS A	1.5	10.8	Short	60	0.0	NA
Lane 2	192	1.0	230	0.834	100	42.6	LOS E	6.5	45.9	Full	500	0.0	0.0
Approach	509	1.0		0.834		20.2	LOS C	6.5	45.9				
North: Verne	y Road												
Lane 1	47	1.0	1844	0.026	100	6.4	LOS A	0.0	0.0	Short	55	0.0	NA
Lane 2	320	3.0	1913	0.167	100	0.0	LOS A	0.0	0.0	Full	450	0.0	0.0
Lane 3	1	1.0	1149	0.001	100	6.9	LOS A	0.0	0.0	Short	30	0.0	NA
Approach	368	2.7		0.167		0.9	NA	0.0	0.0				
West: Ryelar	nd Drive												
Lane 1	37	1.0	97	0.379	100	49.0	LOS E	1.2	8.8	Full	280	0.0	0.0
Approach	37	1.0		0.379		49.0	LOS E	1.2	8.8				
Intersection	1216	1.9		0.834		10.8	NA	6.5	45.9				

Site Level of Service (LOS) Method: Delay (SIDRA). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Lane LOS values are based on average delay per lane.

Minor Road Approach LOS values are based on average delay for all lanes.

NA: Intersection LOS and Major Road Approach LOS values are Not Applicable for two-way sign control since the average delay is not a good LOS measure due to zero delays associated with major road lanes.

SIDRA Standard Delay Model is used. Control Delay includes Geometric Delay.

Gap-Acceptance Capacity: SIDRA Standard (Akçelik M3D).

 $\ensuremath{\mathsf{HV}}$ (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

170769: Shepparton NEGC TIAR Addendum B



Figure B2: LANE SUMMARY

Site: 101v [Verney Road / Ryeland Drive / Access A - PM peak]

New Site

Site Category: (None) Giveway / Yield (Two-Way)

Lane Use a	Lane Use and Performance												
	Demand F Total	lows HV	Сар.	Deg. Satn	Lane Util.	Average Delay	Level of Service	95% Back Veh	of Queue Dist	Lane Config	Lane Length		Prob. Block.
	veh/h	%	veh/h	v/c	%	sec			m		m	%	%
South: Verne	y Road												
Lane 1	28	1.0	1844	0.015	100	6.4	LOS A	0.0	0.0	Short	55	0.0	NA
Lane 2	315	3.0	1897	0.166	100	0.0	LOS A	0.0	0.0	Full	500	0.0	0.0
Lane 3	278	1.0	864	0.322	100	9.4	LOS A	1.6	11.3	Short	45	0.0	NA
Approach	621	2.0		0.322		4.5	NA	1.6	11.3				
East: Access	: A												
Lane 1	119	1.0	966	0.123	100	6.1	LOS A	0.5	3.2	Short	60	0.0	NA
Lane 2	73	1.0	120	0.608	100	50.8	LOS F	2.5	17.3	Full	500	0.0	0.0
Approach	192	1.0		0.608		23.0	LOS C	2.5	17.3				
North: Verne	y Road												
Lane 1	167	1.0	1844	0.091	100	6.4	LOS A	0.0	0.0	Short	55	0.0	NA
Lane 2	311	3.0	1913	0.162	100	0.0	LOS A	0.0	0.0	Full	450	0.0	0.0
Lane 3	3	1.0	1002	0.003	100	7.5	LOS A	0.0	0.1	Short	30	0.0	NA
Approach	481	2.3		0.162		2.3	NA	0.0	0.1				
West: Ryelar	nd Drive												
Lane 1	15	1.0	102	0.145	100	37.9	LOS E	0.4	3.0	Full	280	0.0	0.0
Approach	15	1.0		0.145		37.9	LOS E	0.4	3.0				
Intersection	1308	2.0		0.608		6.8	NA	2.5	17.3				

Site Level of Service (LOS) Method: Delay (SIDRA). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Lane LOS values are based on average delay per lane.

Minor Road Approach LOS values are based on average delay for all lanes.

NA: Intersection LOS and Major Road Approach LOS values are Not Applicable for two-way sign control since the average delay is not a good LOS measure due to zero delays associated with major road lanes.

SIDRA Standard Delay Model is used. Control Delay includes Geometric Delay.

Gap-Acceptance Capacity: SIDRA Standard (Akçelik M3D).

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

170769: Shepparton NEGC TIAR Addendum B



Figure B3: LANE SUMMARY

Site: 101 [Verney Road / Ryeland Drive / Access A - AM peak]

New Site

Site Category: (None)

Signals - Fixed Time Isolated Cycle Time = 80 seconds (Site User-Given Cycle Time)

Lane Use a	nd Perfori	manc	е										
	Demand F	lowe		Dog	Long	Avorago	Lovelof	95% Back	of Oueue	Lane	Lane	Can	Prob.
	Total	HV	Сар.	Deg. Satn	Lane Util.	Delay		95 % Back Veh	Dist		Length		
	veh/h		veh/h	v/c	%	sec	3030	V 011	m		m	%	%
South: Verne	ey Road												
Lane 1	8	1.0	415	0.020	100	32.4	LOS C	0.3	1.8	Short	55	0.0	NA
Lane 2	213	3.0	478	0.445	100	27.8	LOS C	7.1	51.3	Full	500	0.0	0.0
Lane 3	80	1.0	161	0.496	100	46.6	LOS D	3.2	22.6	Short	45	0.0	NA
Approach	301	2.4		0.496		32.9	LOS C	7.1	51.3				
East: Access	s A												
Lane 1	318	1.0	576	0.552	100	25.0	LOS C	9.5	66.9	Short	60	0.0	NA
Lane 2	1	1.0	484	0.002	100	23.8	LOS C	0.0	0.2	Full	500	0.0	0.0
Lane 3	191	1.0	461	0.413	100	32.2	LOS C	6.4	44.9	Short	35	0.0	NA
Approach	509	1.0		0.552		27.7	LOS C	9.5	66.9				
North: Verne	y Road												
Lane 1	47	1.0	415	0.114	100	33.3	LOS C	1.5	10.5	Short	55	0.0	NA
Lane 2	320	3.0	477 1	0.671	100	30.2	LOS C	11.6	83.5	Full	450	0.0	0.0
Lane 3	1	1.0	161	0.007	100	42.8	LOS D	0.0	0.3	Short	30	0.0	NA
Approach	368	2.7		0.671		30.6	LOS C	11.6	83.5				
West: Ryelar	nd Drive												
Lane 1	37	1.0	208	0.177	100	39.5	LOS D	1.2	8.4	Full	280	0.0	0.0
Approach	37	1.0		0.177		39.5	LOS D	1.2	8.4				
Intersection	1216	1.9		0.671		30.2	LOS C	11.6	83.5				

Site Level of Service (LOS) Method: Delay (SIDRA). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Lane LOS values are based on average delay per lane.

Intersection and Approach LOS values are based on average delay for all lanes.

SIDRA Standard Delay Model is used. Control Delay includes Geometric Delay.

Gap-Acceptance Capacity: SIDRA Standard (Akçelik M3D).

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

170769: Shepparton NEGC TIAR Addendum B

¹ Reduced capacity due to a short lane effect. Short lane queues may extend into the full-length lanes. Some upstream delays at entry to short lanes are not included.



Figure B4: LANE SUMMARY

Site: 101 [Verney Road / Ryeland Drive / Access A - PM peak]

New Site

Site Category: (None)

Signals - Fixed Time Isolated Cycle Time = 80 seconds (Site User-Given Cycle Time)

Lane Use a	nd Perfori	manc	е										
	Demand F	Howe		Dog	Lana	A.,	l aval af	05% Pook	of Ouous	Long	Lana	Can	Drob
	Total	HV	Сар.	Deg. Satn	Lane Util.	Delay		95% Back Veh	Dist	Lane	Lane Length		
	veh/h		veh/h	v/c	% %	sec	OCIVICO	VEII	m	Corning	m	/ (aj.	%
South: Verne		70	V 311/11	·/ 0	, ,							70	, , ,
Lane 1	28	1.0	691	0.041	100	23.3	LOS C	0.7	4.9	Short	55	0.0	NA
Lane 2	315	3.0	765	0.411	100	18.6	LOS B	8.9	63.6	Full	500	0.0	0.0
Lane 3	278	1.0	415	0.670	100	38.3	LOS D	10.3	73.0	Short	45	0.0	NA
Approach	621	2.0		0.670		27.6	LOS C	10.3	73.0				
East: Access	s A												
Lane 1	119	1.0	576	0.206	100	23.5	LOS C	3.3	23.1	Short	60	0.0	NA
Lane 2	1	1.0	218	0.005	100	34.2	LOS C	0.0	0.3	Full	500	0.0	0.0
Lane 3	72	1.0	207	0.345	100	41.8	LOS D	2.7	19.2	Short	35	0.0	NA
Approach	192	1.0		0.345		30.4	LOS C	3.3	23.1				
North: Verne	y Road												
Lane 1	167	1.0	415	0.403	100	35.5	LOS D	5.7	40.3	Short	55	0.0	NA
Lane 2	311	3.0	475 1	0.654	100	29.8	LOS C	11.2	80.1	Full	450	0.0	0.0
Lane 3	3	1.0	138	0.023	100	44.5	LOS D	0.1	0.8	Short	30	0.0	NA
Approach	481	2.3		0.654		31.9	LOS C	11.2	80.1				
West: Ryelar	nd Drive												
Lane 1	15	1.0	208	0.071	100	28.2	LOS C	0.4	2.8	Full	280	0.0	0.0
Approach	15	1.0		0.071		28.2	LOS C	0.4	2.8				
Intersection	1308	2.0		0.670		29.6	LOS C	11.2	80.1				

Site Level of Service (LOS) Method: Delay (SIDRA). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Lane LOS values are based on average delay per lane.

Intersection and Approach LOS values are based on average delay for all lanes.

SIDRA Standard Delay Model is used. Control Delay includes Geometric Delay.

Gap-Acceptance Capacity: SIDRA Standard (Akçelik M3D).

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

170769: Shepparton NEGC TIAR Addendum B

¹ Reduced capacity due to a short lane effect. Short lane queues may extend into the full-length lanes. Some upstream delays at entry to short lanes are not included.



Figure B5: LANE SUMMARY

Site: 101 [Verney Road / Pine Street / Access D - AM peak]

New Site

Site Category: (None)

Signals - Fixed Time Isolated Cycle Time = 120 seconds (Site Practical Cycle Time)

Lane Use a	ane Use and Performance												
	Demand F	lows		Deg.	Lane	Average	I evel of	95% Back	of Queue	Lane	Lane	Can	Prob.
	Total	HV	Cap.	Satn	Util.	Delay		Veh	Dist				Block.
	veh/h		veh/h	v/c	%	sec			m		m	%	%
South: Vern	ey Road												
Lane 1	141	1.0	400	0.353	100	49.6	LOS D	7.1	49.8	Short	45	0.0	NA
Lane 2	319	3.0	3931	0.812	100	49.9	LOS D	18.4	132.3	Full	500	0.0	0.0
Lane 3	147	1.0	215	0.685	100	64.1	LOS E	8.7	61.5	Short	65	0.0	NA
Approach	607	2.1		0.812		53.3	LOS D	18.4	132.3				
East: Acces	s D												
Lane 1	589	1.0	683 ₁	0.863	100	39.2	LOS D	30.6	215.9	Short	75	0.0	NA
Lane 2	482	1.0	469 ₁	1.028	100	114.5	LOS F	46.6	328.8	Full	500	0.0	0.0
Lane 3	1	1.0	630	0.002	100	31.7	LOS C	0.0	0.3	Short	75	0.0	NA
Approach	1073	1.0		1.028		73.0	LOS E	46.6	328.8				
North: Verne	ey Road												
Lane 1	1	1.0	400	0.003	100	45.1	LOS D	0.0	0.3	Short	30	0.0	NA
Lane 2	467	3.0	452 1	1.033	100	116.1	LOS F	43.9	315.4	Full	500	0.0	0.0
Lane 3	16	1.0	215	0.073	100	57.7	LOS E	0.8	5.9	Short	40	0.0	NA
Approach	484	2.9		1.033		114.1	LOS F	43.9	315.4				
West: Pine S	Street												
Lane 1	162	1.0	189	0.859	100	75.3	LOS E	10.4	73.3	Full	145	0.0	0.0
Approach	162	1.0		0.859		75.3	LOS E	10.4	73.3				
Intersection	2326	1.7		1.033		76.6	LOS E	46.6	328.8				

Site Level of Service (LOS) Method: Delay (SIDRA). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Lane LOS values are based on average delay per lane.

Intersection and Approach LOS values are based on average delay for all lanes.

SIDRA Standard Delay Model is used. Control Delay includes Geometric Delay.

Gap-Acceptance Capacity: SIDRA Standard (Akçelik M3D).

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

170769: Shepparton NEGC TIAR Addendum B

¹ Reduced capacity due to a short lane effect. Short lane queues may extend into the full-length lanes. Some upstream delays at entry to short lanes are not included.



Figure B6: LANE SUMMARY

Site: 101 [Verney Road / Pine Street / Access D - PM peak]

New Site

Site Category: (None)

Signals - Fixed Time Isolated Cycle Time = 120 seconds (Site Practical Cycle Time)

Lane Use a	nd Perforr	nanc	е										
	Demand F	lowe		D	1	A	Lavalat	0E9/ Book	of Ougus	1	1	0	Durch -
	Total	HV	Сар.	Deg. Satn	Lane Util.	Average		95% Back Veh	Dist	Lane	Lane Length		Prob. Block.
	veh/h		veh/h	v/c	% %	sec	Oct vice	Veli	Dist m	Corning	m	۸uj. %	%
South: Verne		/0	VG11/11	V/C	/0	360			- '''			/0	/0
Lane 1	197	1.0	353	0.557	100	54.4	LOS D	10.6	74.8	Short	45	0.0	NA
Lane 2	488	3.0		1.438	100	448.7	LOS F	93.8	673.6	Full	500	0.0	<mark>39.4</mark> 8
Lane 3	516	1.0	3491	1.479	100	491.5	LOS F	103.2	728.4	Short	65	0.0	NA
Approach	1201	1.8		1.479		402.5	LOS F	103.2	728.4				
East: Access	. D												
Lane 1	221	1.0	553	0.400	100	38.6	LOS D	10.0	70.8	Short	75	0.0	NA
Lane 2	181	1.0	194	0.935	100	76.6	LOS E	12.8	90.3	Full	500	0.0	0.0
Lane 3	1	1.0	184	0.006	100	56.9	LOS E	0.1	0.4	Short	75	0.0	NA
Approach	403	1.0		0.935		55.7	LOS E	12.8	90.3				
North: Verne	y Road												
Lane 1	1	1.0	353	0.003	100	47.8	LOS D	0.0	0.3	Short	30	0.0	NA
Lane 2	400	3.0	405 1	0.988	100	91.5	LOS F	32.8	235.5	Full	500	0.0	0.0
Lane 3	16	1.0	415	0.038	100	44.9	LOS D	0.7	5.1	Short	40	0.0	NA
Approach	417	2.9		0.988		89.7	LOS F	32.8	235.5				
West: Pine S	treet												
Lane 1	702	1.0	486	1.443	100	445.0	LOS F	127.5	900.1	Full	145	0.0	100.0
Approach	702	1.0		1.443		445.0	LOS F	127.5	900.1				
Intersection	2723	1.7		1.479		314.2	LOS F	127.5	900.1				

Site Level of Service (LOS) Method: Delay (SIDRA). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Lane LOS values are based on average delay per lane.

Intersection and Approach LOS values are based on average delay for all lanes.

SIDRA Standard Delay Model is used. Control Delay includes Geometric Delay.

Gap-Acceptance Capacity: SIDRA Standard (Akçelik M3D).

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

170769: Shepparton NEGC TIAR Addendum B

¹ Reduced capacity due to a short lane effect. Short lane queues may extend into the full-length lanes. Some upstream delays at entry to short lanes are not included.

⁸ Probability of Blockage has been set on the basis of a queue that overflows from a short lane.



ATTACHMENT C - IDM URBAN ROAD STANDARDS

Figure C1: Table 2 from Council's Infrastructure Design Manual

INFRASTRUCTURE DESIGN MANUAL

TABLE 2 - URBAN ROAD / STREET CHARACTERISTICS

Street Type	Indicative Maximum Traffic Volume	Carriageway Width	Minimum Reserve Width See Note 5 & 6	Minimum Verge Width	Parking Provision within Carriageway	Pedestrian / Cycle Provision within Road Reserve	Kerbing
Access Lane (second road frontage)	300 veh/day	5.5m	As determined by turning movements		Yes one side	No footpath	Nil if concrete road with central drain or SM2 or modified SM2 See note 3
Access Place	300 veh/day max. (maximum length 100m)	6.0m	14.0m	3.5m See Note 2	Yes (one side)	Footpath both sides No separate cycle provision	B2,SM2 or modified SM2 See note 3
Access Street	1000 veh/day max	7.5m	16.0m	3.5m See Note 2	Yes (both sides)	Footpath both sides No separate cycle provision	B2, SM2 or modified SM2 See note 3
Collector/Connector Street Level 1	3000 veh/day max	11.0m	24.0m	6.0m	Yes (both sides)	Shared path both sides	Barrier B2 Kerb outstands or splitters required at intersections and pedestrian crossing points
Collector/Connector Street Level 2 (alternatively called trunk collector)	6000 veh/day max	2 x 7.0m + 5.0m median	34.0m	6.0m	Yes (both sides)	Footpath both sides Shared path both sides	Barrier B2
Residential Court Bowl	n/a	10,0m radius	28.0m	3.5m See Note 2	n/a	Footpath both sides No separate cycle provision	SM2 or modified SM2 See note 3
Commercial Street	n/a	22.0m	32. 0m	5.0m	Yes (both sides)	Fcotpath both sides Cycle provision where directed	Barrier B2
Industrial Street	n/a	12.5m See Note 1 below	25 .0m	6.0m See Note 4	Yes (both sides)	Yes	Barrier B2
Industrial Court Bowl	n/a	15.0m radius	37.0m	3.5m	n/a	п/а	Barrier B2

170769: Shepparton NEGC TIAR Addendum B



ATTACHMENT D - TRAFFIC ESTIMATES

Figure D1: 2014 Traffic Generation Estimates (based on 80%/20% split in AM) and a yield of 11 lots/ha

Precinct /	Area	Lots	Peak Traffic	Distribution	1	Prescinct		Orienta	ation			
1	(ha)	@ 11/ha		Split Access P	oint	Totals	AM		PI	VI .	AM orientation split	
				Direction	woh	(voh)	IN (DUT	IN (70%)	OUT (30%)	IN 20% OUT 80%	
			(vph)	Direction	VpII	(vpii)	(20/8)	3070)	(7070)	(30%)	1N 20% OU1 80%	
Stage 1: only pred	cincts 6	& 7 and 0	community hub	developed with all	l traffic	via access A	4					
	18.16	200	160	100% A (west)	160						Stage 1 Internal Traffic Volumes	
	8.626	95		100% A (west)							vph vpd Road Class	
Comm. Hub 13	350m²	205	169 404		17	253	51	202	177	76	Access A 253 2526 Collector Level 1	
		295	404									
Stage 2: precincts	s 6. 7 &	1 and cor	mmunity hub de	eveloped with traff	ic split	between ac	cess A & I	3			Peak Turn Movements at each Access Peak Through Traffic	Indicative Turn Treatment
	18.16	200	160	92% A (west)	147						Dir Split Dir Split Verney Road (2008 x 1.2)	At Access A
	8.626	95	76	92% A (west)	70						IN 5/25 OUT 5/25 AM PM	QL QR QT1 QT2 QM Treatment
Comm. Hub 13			169		17						Access A 294 49 N 336 56 N 202 NB 299 NB	
	23.04	253	203 160	,,	187		84	336	294	126	245 S 280 S 304 SB 245 SB Hawkins from 177 W to 202 W 505 Σ 544 Σ	56 280 245 299 600 CHR & AUL(S)
	18.16 8.626	200 95	76		13		-	-			Hawkins from 177 W to 202 W 505 Σ 544 Σ 69 S 78 S	At Hawkins Street
	23.04	253	203		16	35	7	28	25	11	03 3 70 3	QL QR QT1 QT2 QM Treatment
		548	438			455					Stage 2 Internal Traffic Volumes	
											vph vpd Road Class	0 177 304 202 505 CHR
				nd school included,			en access	A, B 8	k C		Access A 420 4203 Trunk Collector	
	18.16 8.626	200 95	160 76		101						Access B 35 351 Access Street	
	8.626 350m²	95	169		17			-				
	23.04	253	203		128							
	25.04	275	220		139			_			Peak Turn Movements at each Access Peak Through Traffic	Indicative Turn Treatment
	17.01	187	150	63% A (west)	94						Dir Split Dir Split Verney Road (2008 x 1.2)	At Access A
	13.67	150	120		76						IN 5/25 OUT 5/25 AM PM	QL QR QT1 QT2 QM Treatment
	11.11	122	98		62		133	531	465	199	Access A 465 77 N 531 88 N 202 NB 299 NB	00 442 245 205
	18.16 8.626	200 95	160 76		13	-	\vdash				387 S 442 S 304 SB 245 SB Hawkins from 279 W to 319 W 505 Σ 544 Σ	88 442 245 299 632 CHR & AUL(S)
	23.04	253	203		16		\vdash	-+			108 S 124 S	At Hawkins Street
	25.04	275	220		18			- t			•	QL QR QT1 QT2 QM Treatment
3	17.01	187	150	8% B (north)	12			二			Stage 3 Internal Traffic Volumes	
	13.67	150	120		10			П			vph vpd Road Class	0 279 304 202 505 CHR
	11.11	122	98 160		8		16	66	57	25	Access A 664 6636 Trunk Collector	
	18.16 8.626	200 95	160 76		46 22		-	-			Access B 82 821 Access Street Access C 533 5327 Trunk Collector	
	23.04	253	203		59			-			Access C 555 5527 Trunk Conector	
	25.04	275	220		64							
Grahamvale 60	00 stude	ents									Peak Turn Movements at each Access Peak Through Traffic	Indicative Turn Treatment
	35 staf		635		235						Grahamvale Road (2003 x 1.2)	
	17.01	187	150		43						Dir Split Dir Split AM PM	QL QR QT1 QT2 QM Treatment
	13.67	150 122	120		35		204	332	202	220	Access C IN 2/27 OUT 2/27 226 NB 271 NB	407 44 242 274 700 000 0 400
5	11.11	1283	1242	29% C (east) 100%	28	533 1278	201	332	302	230	AM 201 14 N 332 23 N 269 SB 242 SB 187 S 309 S 494 Σ 514 Σ	187 14 242 271 700 CHR & AUL
		1203	12-12	100%	<u> </u>	1270		-			PM 302 21 N 230 16 N	
Stage 4: all precir	ncts, hu	b and sch	ool fully develo	ped with traffic spl	lit betw	veen access	A, B, C &)			282 S 214 S	
	18.16	200	160									
	8.626	95	76		23		_	_				
Comm. Hub 13	23.04	253	169 203		17 61		-	-				
	25.04	275	220		66							
3	17.01	187	150		45							
4	13.67	150	120	30% A (west)	36						Stage 4 Internal Traffic Volumes	
	11.11	122	98		29						vph vpd Road Class	
	18.23	201	160		48		04	224	204	422	Access A 405 4052 Trunk Collector	
	12.22 18.16	134 200	108 160		32 13	405	81	324	284	122	Access B 104 1036 Collector Level 1 Access C 579 5786 Trunk Collector	
	8.626	95	76		6		+	+			Access D 459 4589 Trunk Collector	
	23.04	253	203		16			-1			15464	
	25.04	275	220		18							
	17.01	187	150		12			[Peak Turn Movements at each Access Peak Through Traffic	Indicative Turn Treatment
	13.67	150	120 98		10		\vdash				Ford Road (2010 x 1.16)	0. 0. 0. 0. 0. 0.
	11.11	122 201	98 160		13	-	\vdash	-+			Dir Split Dir Split AM PM Access B IN 100% OUT 100% 242 EB 147 EB	QL QR QT1 QT2 QM Treatment
-	12.22	134	108		9		21	83	72	31	AM 21 21 E 83 83 E 172 WB 187 WB	21 147 187 187 AUL(S)
	18.16	200	160		46			_1			PM 72 72 E 31 31 E 414 Σ 334 Σ	
7	8.626	95	76	29% C (east)	22							
	23.04	253	203		59							
Grahamvale 60	25.04	275	220	29% C (east)	64		\vdash					
Grahamvale 60 School sta		nts + 35	635	32% C (east)	203							
	17.01	187	150		43		\vdash	\dashv				
	13.67	150	120	29% C (east)	35						Grahamvale Road (2003 x 1.2)	
5	11.11	122	98	29% C (east)	28						Dir Split Dir Split AM PM	QL QR QT1 QT2 QM Treatment
	18.23	201	160		47		\Box	\Box			Access C IN 2/27 OUT 2/27 226 NB 271 NB	
	12.22	134	108		31	579	171	364	327	209	AM 171 12 N 364 25 N 269 SB 242 SB	159 12 242 271 673 CHR & AUL
	18.16 8.626	200 95	160 76		53 25		+	+			159 S 339 S 494 Σ 514 Σ PM 327 23 N 209 14 N	
	23.04	253	203		67		+	-+			304 S 194 S	
	25.04	275		33% D (west)	73						· · · · · · · · · · · · · · · · · · ·	
Grahamvale 60	00 stude							T				
School sta			635		32			[
	17.01	187	150	33% D (west) 33% D (west)	49		$\vdash \vdash$	[Dir Split Dir Split	
	13.67 11.11	150 122		33% D (west) 33% D (west)	40 32		+				Access D IN 8/25 OUT 8/25 Verney Road (2008 x 1.2) AM 131 32 S 372 90 S AM PM	QL QR QT1 QT2 QM Treatment
	18.23	201		33% D (west)	53		+	-1			99 W 282 W 202 NB 299 NB	a, an air air am treatment
10		134		33% D (west)	35	459	131	372	329	174	0 N 0 N 304 SB 245 SB	0 90 299 245 544 CHR
		1618	1510	100%		1546					PM 329 80 S 174 42 S 505 Σ 544 Σ	
				-							250 W 132 W	
											0 N 0 N	

170769: Shepparton NEGC TIAR Addendum B



Figure D2: 2018 Traffic Generation Estimates (based on closure of Accesses B and C) and a yield of 10 lots/ha

	/h-\	Lots	Peak Traffic	Culle	Distributio	on Delet	Prescinct		Orien	tation				ccess B &							_	-					
		@ 10/ha		Split				IN	OUT	IN	OUT	AN	INI	20%	OUT	80%											
			(vph)		Direction		(vph)	(20%)	(80%)	(70%)	(30%)	PIV		70%		30%											
1: only 6		s 6, 7, par 182	t 8 and commi 145		nub develo (A (west)		th all traff	ic via a	ccess A		\vdash	Stage 1 In	ternal	Traffic \	/olume	es es	-					\dashv					
7	8.626 5.00	86 50	69	100%	A (west) A (west)	69					\Box	Access A	vph 271			Class						-				П	
m. Hub			169	10%	A (west)		271	54	217	190	81	Access A	2/1	2712	Cone	ctor Level 1											
		318	423			+			Н		\vdash						-				-	\dashv				Н	
2: prec		, 8, 1 and 182	community hu	ib dev	eloped wi	ith all to		cess A				Peak Tur	n Mov	roments	at eac	h Accoss	Poak	Thro	ugh Traf	fic		Indic	ative	Tur	o Tro	atmer	nt
7	8.626	86	69	100%	A (west)	69						reak rui	Dir	Split	Dir	Split	Vern	ey Ro	ad (2008		-	At Ac	cess	Α			
m. Hub		50	40 169		A (west) A (west)				\vdash		$\vdash\vdash$	Access A	IN 319	5/25 53 N	OUT 1 364	5/25 61 N	AM 202	NB	PM 299 I	NB							Treatment signals or
1	23.04	230		100%	A (west)	184	455	91	364	319	137	Unividan		266 9		304 S	304	SB	245	SB		_					roundabou
6 7	18.16 8.626	182 86	145 69		B (north) B (north)						\vdash	Hawkins	trom	191 V		219 W 85 S	505	2	544	2		-					
8	5.00 23.04	50 230	40 184		B (north)			0	0	0	0											At Ha				Ou	Treatment
	25.04	548		100%			455				٣	Stage 2 In															
3: prec	incts 6, 7	, 8, 1, 2, 3	, 4 & 5 develo	oed, a	II traffic vi	a acces	s A but sch	ool to (Graham	vale Ro	d d	Access A	vph 455	vpd 4555		Class ector Level 1					PM	0	219	245	299	544	signals or i
6	18.16	182	145	100%	A (west)	145						Access B	0	0		ccess						\Box					
8	8.626 5.00	86 50			A (west) A (west)																	\rightarrow					
m. Hub 1		230			A (west) A (west)						\Box																
2	25.04	250	200	100%	A (west)	200						Peak Tur							ugh Traf						n Tre	atmer	nt
3 4	_	170 137			A (west) A (west)				Н	-	\vdash			Split 13/25		Split 13/25	Vern		ad (2008 PM	8 x 1.2)		At Ac			QT2	Qм	Treatmen
5	11.11	111	89	100%	A (west)	89	990	198	792	693	297	Access A	693	237 1	792	271 N	202	NB	299								
6 7		182 86	145 69		B (north) B (north)				H		$\vdash \vdash$	Hawkins	from	456 S		521 S 375 W	304 505	SΒ	245 5 544 2			271	521	245	299	815	signals or
8	5.00	50 230	40 184	0%	B (north)	0					\square			128 9		146 S	T					At Ha	awbi.	ns C+	reet	\Box	
2	25.04	250	200	0%	B (north)	0					\boxminus															Ом	Treatmer
3	17.01 13.67	170 137	136 109		B (north) B (north)				H	\Box	$\vdash \vdash$	Stage 3 In	ternal vph			l Class						0	328	304	202	505	signals or
5	11.11	111	89	0%	B (north)	0	0	0	0	0	0	Access A	990	9901	Trun	k Collector											J .2.3 01
6 7	18.16 8.626	182 86	145		C (east)	0					\vdash	Access B Access C	635	0		ol Access only					-	-					
8	5.00	50 230	40 184	0%	C (east)	0																\Box					
1 2	_	250	200		C (east)	0					$\vdash \vdash$				-							\dashv					
mvale I	600 stud + 35 staf		625	100%	6 C (east)	635						Peak Tur	n Mov	ements	at eac	h Access			ugh Traf	fic (2003 x 1.2)		Indic	ative	Turr	n Tre	atmer	nt
3	17.01	170	136	0%	C (east)	0							Dir			Split	AM		PM			QL I	QR	Q _{T1}	Q _{T2}	Ом	Treatmen
- 4 5	20.0.	137 111	109		C (east)	0	635	381	254	254	381	School Access AM	IN 381	2/27 26 N	OUT 254	2/27 18 N	226	NB SB	271		-	355	26	242	271	868	signals or
		1217		100%		Ť	1625	501	251	254	301			355 9		236 S	494		514			333				000	31611013 01
4: all pi	recincts,	hub and	school fully de	velop	ed with tr	affic sp	lit betwee	n acces	s A & D		\vdash	PM	254	18 M		26 N 355 S	-				-	-					
6	18.16	182	145	100%	A (west)	145																\equiv					
7 8	8.626 5.00	86 50			A (west) A (west)				Н		\vdash				-		-					+				\vdash	
m. Hub 1	1350m² 23.04	230		10%	A (west)	17					\Box											=					
2		250			A (west) A (west)																						
3 4	_	170 137	136 109		A (west) A (west)						\Box	Stage 4 In	terna	(2 way)	Traffic	Volumes											
5	11.11	111	89	0%	A (west)	0							vph	vpd	Road	l Class											
9 10		182		0%	A (west) A (west)		604	121	484			Access A Access B	604			k Collector ccess						-					
	-00	122	146 98							423	181		0	0							_						
6	12.22 18.16	182	98 145	0%	B (north)		- 004			423	181	Access C	0	0		ccess					_						
6 7 8	12.22 18.16 8.626		98	0% 0%		0				423	181	Access C Access D	0	0		ccess eds Trunk Collecto	or										
7 8 1	12.22 18.16 8.626 5.00 23.04	182 86 50 230	98 145 69 40 184	0% 0% 0% 0% 0%	B (north) B (north) B (north) B (north) B (north)	0 0				423	181		0	0			or										
7 8	12.22 18.16 8.626 5.00 23.04	182 86 50	98 145 69 40	0% 0% 0% 0% 0%	B (north) B (north) B (north)	0 0 0 0 0 0				423	181		1272	0 12467 18511	Exce	eds Trunk Collecto	Peak		ugh Traf			Indica	ative	Turr	n Tre	atmer	nt
7 8 1 2 3 4	12.22 18.16 8.626 5.00 23.04 25.04 17.01 13.67	182 86 50 230 250 170 137	98 145 69 40 184 200 136	0% 0% 0% 0% 0% 0% 0%	6 B (north) 6 B (north) 6 B (north) 6 B (north) 6 B (north) 6 B (north) 6 B (north)	0 0 0 0 0 0 0 0 0 0 0 0 0 0				423	181	Access D	0 1272	0 12467 18511	Exce at eac	eds Trunk Collecto	Peak Ford	Road	(2010 x								
7 8 1 2 3 4 5	12.22 18.16 8.626 5.00 23.04 25.04 17.01 13.67 11.11 18.23	182 86 50 230 250 170 137 111 182	98 145 69 40 184 200 136 109 89	0% 0% 0% 0% 0% 0% 0% 0% 0%	6 B (north) 6 B (north)	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0						Peak Tur Access B	n Mov	0 12467 18511 rements Split 100%	at each	eds Trunk Collecte h Access Split 100%	Peak Ford AM 242	Road	(2010 x PM 147 I	1.16) EB		QL (QR	Q _{T1}	Q _{T2}	Q _M	Treatmer
7 8 1 2 3 4 5 9	12.22 18.16 8.626 5.00 23.04 25.04 17.01 13.67 11.11 18.23 12.22	182 86 50 230 250 170 137 111	98 145 69 40 184 200 136 109	0% 0% 0% 0% 0% 0% 0% 0% 0% 0%	6 B (north)) 0) 0) 0) 0) 0) 0) 0) 0) 0	0	0	0			Access D Peak Tur	0 1272	0 12467 18511 rements Split 100% 0 E	at eac	h Access Split 100% 0 E	Peak Ford AM 242	Road EB WB	(2010 x PM 147 I	1.16) EB WB		QL (QR	Q _{T1}	Q _{T2}		Treatme
7 8 1 2 3 4 5 9 10 6	12.22 18.16 8.626 5.00 23.04 25.04 17.01 13.67 11.11 18.23 12.22 18.16 8.626	182 86 50 230 250 170 137 111 182 122 182	98 145 69 40 184 200 136 109 89 146 98 145 69	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0%	6 B (north) 6 C (east) 6 C (east)) 0 0 0 0 0 0 0 0 0 0 0 0 0	0	0	0			Peak Tur Access B AM	0 1272 n Mov Dir IN	0 12467 18511 rements Split 100% 0 E	at eac	h Access Split 100% 0 E	Peak Ford AM 242	Road EB WB	(2010 x PM 147 I 187 I	1.16) EB WB		QL (QR	Q _{T1}	Q _{T2}	Q _M	Treatme
7 8 1 2 3 4 5 9	12.22 18.16 8.626 5.00 23.04 25.04 17.01 13.67 11.11 18.23 12.22 18.16 8.626 5.00	182 86 50 230 250 170 137 111 182 122	98 145 69 40 184 200 136 109 89 146 98	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	6 B (north) 6 C (east)	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0	0	0			Peak Tur Access B AM	0 1272 n Mov Dir IN	0 12467 18511 rements Split 100% 0 E	at eac	h Access Split 100% 0 E	Peak Ford AM 242	Road EB WB	(2010 x PM 147 I 187 I	1.16) EB WB		QL (QR	Q _{T1}	Q _{T2}	Q _M	Treatme
7 8 1 2 3 4 5 9 10 6 7 8	12.22 18.16 8.626 5.00 23.04 25.04 17.01 13.67 11.11 18.23 12.22 18.16 8.626 5.00 23.04	182 86 50 230 250 170 137 111 182 122 182 86 50 230	98 145 69 40 184 200 136 109 89 146 98 145 69	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	6 B (north) 6 C (east) 6 C (east)	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0	0	0			Peak Tur Access B AM	0 1272 n Mov Dir IN	0 12467 18511 rements Split 100% 0 E	at eac	h Access Split 100% 0 E	Peak Ford AM 242	Road EB WB	(2010 x PM 147 I 187 I	1.16) EB WB		QL (QR	Q _{T1}	Q _{T2}	Q _M	Treatme
7 8 1 2 3 4 5 9 10 6 7 8 1 2 mvale	12.22 18.16 8.626 5.00 23.04 25.04 17.01 13.67 11.11 18.23 12.22 18.16 8.626 5.00 23.04 25.04 600 stud 35 staff	182 86 50 230 250 170 137 111 182 122 182 86 50 230 250 ents +	98 145 699 400 408 1284 1284 1290 1099 899 1466 986 699 400 408 184 200	0999 0990 0990 0990 0990 0990 0990 099	6 B (north) 6 C (east) 6 C (east) 6 C (east) 6 C (east)	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0	0	0			Peak Tur Access B AM	0 1272 n Mov Dir IN	0 12467 18511 rements Split 100% 0 E	at eac	h Access Split 100% 0 E	Peak Ford AM 242	Road EB WB	(2010 x PM 147 I 187 I	1.16) EB WB		QL (QR	Q _{T1}	Q _{T2}	Q _M	Treatmer
7 8 1 2 3 4 5 9 10 6 7 8 1 2 mvale	12.22 18.16 8.626 5.00 23.04 25.04 17.01 13.67 11.11 18.23 12.22 18.16 8.626 5.00 23.04 25.04 600 stud 35 staff 17.01	182 86 50 230 250 170 137 111 182 122 182 86 50 230 250	98 145 145 695 94 400 400 1384 1384 1399 98 98 98 98 98 40 40 40 40 635 136	0%0 0%0 0%0 0%0 0%0 0%0 0%0 0%0 0%0 0%0	6 B (north) 6 C (east)	0 0 0 0 0	0	0	0			Peak Tur Access B AM	0 1272 n Mov Dir IN	0 12467 18511 rements Split 100% 0 E	at eac	h Access Split 100% 0 E	Peak Ford AM 242 172 414	Road EB WB Σ	(2010 x PM 147 I 187 V 334 I	1.16) EB WB Σ	PM	QL (QR	Q _{T1}	Q _{T2}	Q _M	Treatme
7 8 8 1 2 2 3 3 4 4 5 5 9 10 6 6 7 8 8 1 1 2 2 mvale 3 4 5 5	12.22 18.16 8.626 5.00 23.04 25.04 17.01 13.67 118.23 12.22 18.16 8.626 25.04 600 stud 35 staff 17.01 13.67 11.11	182 86 50 230 250 137 111 182 122 182 230 230 ents +	98 145 145 146 199 140 140 140 140 140 140 140 140 140 140	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	6 B (north) 6 C (east)	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0	0	0			Peak Tur	0 0 1272	0 12467 18511 Split 100% 0 E 0 E	Exce Dir OUT 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	h Access Split 100% 0 E 0 E	Peak Ford AM 242 172 414	Road EB WB Σ	(2010 x PM 147 I 187 V 334 I	1.16) EB WB Σ	PM	O _L (Q _R	Q ₇₁	Q ₁₂	Q _M '187	Treatmen
7 8 1 2 3 4 5 9 10 6 7 8 1 2 2 mvale 3 4 4	12.22 18.16 8.626 23.04 25.04 17.01 13.67 11.11 18.23 12.22 18.16 8.626 5.00 23.04 25.04 600 stud 35 staff 17.01 13.11 1	182 86 50 230 250 170 137 131 182 122 182 20 230 250 ents +	98 145 696 98 140 400 1306 1306 1306 98 145 145 146 146 146 146 146 146 146 146 146 146	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	6 B (north) 6 C (east) 7 C (east) 7 C (east) 7 C (east) 8 C (east) 8 C (east) 9 C (east)	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0	0		0	0	Peak Tur Access B AM	0 0 1272	0 12467 18511 Split 100% 0 E 0 E Split 2/27	Exce Dir OUT OUT Dir OUT OUT OUT OUT	h Access Split 100% 0 E 0 E Split 2/27	Peak Ford AM 242 172 414	Road EB WB Σ	(2010 x PM 147 I 187 V 334 I	1.16) EB WB Σ (2003 x 1.2)	PM	Q _L (Q _R 0	Qr1 147 Qr1	Q ₁₂	Q _M '187	Treatme:
77 88 11 22 33 44 55 99 100 66 77 88 11 22 novale 33 44 55 99 100 66	12.22 18.16 8.626 5.00 23.04 25.04 17.01 13.67 11.11 18.23 18.16 8.626 5.00 23.04 25.04 600 stud 35 staff 17.01 13.67 11.11 18.23 17.01 13.67 11.11 18.23 17.01 13.67 11.11	182 86 50 230 250 170 137 111 182 122 182 86 230 230 250 ents +	98 145 69 69 69 69 69 69 69 69 69 69 69 69 69	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	6 B (north) 6 C (east) 7 C (east) 7 C (east) 8 C (east) 9 C (east)		0			0	0	Access D Peak Tur Access B AM PM Access C AM	Dir IN O	0 0 12467 18511 18511 100% 0 E 0 E Split 100% Split 100% 0 E 0 E 0 E 0 E 0 E 0 E 0 E 0 E 0 E	Exce Dir OUT 0 0 Dir Out 0 0 0 0 0 0 0 0 0 0 0 0 0	## Access	Peak Ford AM 242 172 414	Road EB WB Σ	(2010 x PM 147 I 187 I 334 2	1.16) EB WB Σ (2003 x 1.2) NB SS	PM	OL 0	Q _R 0	Q _{T1} 147 Q _{T1} 269	Q ₁₂ 187 Q ₁₂ Q ₁₂ Q ₁₂ Q ₁₂ Q ₁₂ 226	Q _м 187	Treatment Treatment Nil
7 7 8 1 1 2 2 3 3 4 4 5 5 9 10 6 6 7 7 8 8 1 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	12.22 18.16 8.626 5.00 23.04 17.01 13.67 11.11 18.23 12.22 25.04 600 stud 35 staff 17.01 18.23 12.21 12.22 12.23 12.21 13.67 13.67 14.11 18.23 17.01 18.23 18.24 18.25 1	182 86 50 230 170 177 111 182 182 182 250 ents +	98 98 98 98 89 98 88	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	6 B (north) 6 C (east) 7 C (east) 7 C (east) 8 D (east) 8 D (east) 9 C (east)		0			0	0	Peak Tur Access B AM PM Access C	Dir IN O	0 0 12467 18511 18511 100% 0 E 0 E Split 2/27 0 N 0 S	Exce at eacl Dir OUT 0 0 Dir OUT 0 0 0 0 0 0 0 0 0 0 0 0 0	Access Split 100% 0 E 0 E Split 2/27 0 N 0 S	Peak Ford AM 242 172 414 Grah AM 226 269	Road EB WB Σ	(2010 x PM 147 I 187 I 334 2 le Road PM 271 I 242 2	1.16) EB WB Σ (2003 x 1.2) NB SS	PM)	OL 0	Q _R 0	Q _{T1} 147 Q _{T1} 269	Q ₁₂ 187 Q ₁₂ Q ₁₂ Q ₁₂ Q ₁₂ Q ₁₂ 226	Q _M 187	Treatment Treatment Nil
7 7 8 1 1 2 3 3 4 4 5 9 9 10 6 6 7 7 8 9 10 6 6 7 7 8 1 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	12.22 18.16 5.00 23.04 25.04 17.01 13.67 11.11 18.23 12.22 18.16 600 stud 35 staff 17.01 18.67 11.11 18.23 12.22 18.16 8.626 5.00 23.04	182 866 50 230 250 170 131 111 182 122 22 86 50 250 250 250 250 250 250 250 250 250	98 98 98 98 99 99 99 99 99 99 99 99 99 9	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	6 B (north) 6 C (east) 7 C (east) 7 C (east) 8 C (east) 8 C (east) 9 C (east)		0			0	0	Access D Peak Tur Access B AM PM Access C AM	Dir IN O	0 0 12467 18511 100% 0 E 0 E 0 1 12467 1 18511 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Exce at eacl Dir OUT 0 0 Dir OUT OUT OUT OUT OUT OUT OUT OU	eds Trunk Collecte h Access Split 100% 0 E 0 E Split 2/27 0 N 0 S 0 N	Peak Ford AM 242 172 414 Grah AM 226 269	Road EB WB Σ	(2010 x PM 147 I 187 I 334 2 le Road PM 271 I 242 2	1.16) EB WB Σ (2003 x 1.2) NB SS	PM)	OL 0	Q _R 0	Q _{T1} 147 Q _{T1} 269	Q ₁₂ 187 Q ₁₂ Q ₁₂ Q ₁₂ Q ₁₂ Q ₁₂ 226	Q _M 187	Treatment Treatment Nil
77 88 11 22 33 44 59 10 66 77 88 11 22 mivale 33 44 55 99 10 66 77 88 11 22 10 67 88 11 22 10 68 78 88 11 22 10 68 78 88 11 22 28 28 28 28 28 28 28 28 28 28 28 28	12.22 18.16 8.626 5.00 23.04 17.01 13.67 11.11 18.23 12.22 18.16 5.00 23.04 35 staff 17.01 13.67 17.01 19.22 19.25	182 866 500 1377 1377 1111 182 122 122 122 122 1250 615 5 500 615 5 615 615 615 615 615 615 615 615 6	98 98 1454 69 69 40 40 40 40 40 40 40 40 40 40 40 40 40	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	6 B (north) 6 C (east) 7 C (east) 7 C (east) 8 D (east) 8 D (east) 9 C (east)		0			0	0	Access D Peak Tur Access B AM PM Access C AM	Dir IN O	0 0 12467 18511 100% 0 E 0 E 0 1 12467 1 18511 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Exce at eacl Dir OUT 0 0 Dir OUT OUT OUT OUT OUT OUT OUT OU	eds Trunk Collecte h Access Split 100% 0 E 0 E Split 2/27 0 N 0 S 0 N	Peak Ford AM 242 172 414 Grah AM 226 269	Road EB WB Σ	(2010 x PM 147 I 187 I 334 2 le Road PM 271 I 242 2	1.16) EB WB Σ (2003 x 1.2) NB SS	PM)	OL 0	Q _R 0	Q _{T1} 147 Q _{T1} 269	Q ₁₂ 187 Q ₁₂ Q ₁₂ Q ₁₂ Q ₁₂ Q ₁₂ 226	Q _M 187	Treatmen Nil Treatmen
77 88 11 22 33 44 55 99 100 66 77 88 11 2 2 movale 1 7 8 1 2 2 movale 1 2 2 movale 1 2 2	12.22 18.16 8.626 5.00 17.01 13.67 11.11 18.23 12.25 0.04 17.01 13.67 11.11 18.23 12.22 13.04 12	182 86 6 5 9 1 12 12 12 182 86 6 5 9 1 10 1 11 1 1 1 1 1 1 1 1 1 1 1 1 1 1	98 98 98 145 145 146 146 146 146 146 146 146 146 146 146	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	is le north) B (north) B	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0			0	0	Access D Peak Tur Access B AM PM Access C AM	Dir IN 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 12467 18511 100% O E O E O E O E O E O E O E O E O E O	at eac	split 2/27 ON OS	Peak Ford AM 242 172 414 Grah AM 226 269	Road EB WB Σ	(2010 x PM 147 I 187 I 334 2 le Road PM 271 I 242 2	1.16) EB WB Σ (2003 x 1.2) NB SS	PM)	OL 0	Q _R 0	Q _{T1} 147 Q _{T1} 269	Q ₁₂ 187 Q ₁₂ Q ₁₂ Q ₁₂ Q ₁₂ Q ₁₂ 226	Q _M 187	Treatmen Nil Treatmen
77 88 11 23 34 45 5 910 66 77 88 11 22 movale 1 3 4 5 9 10 6 7 7 8 8 1 2 movale 1 2 movale 1 3 4 4 5 9 10 6 7 8 8 1 4 4 5 9 10 6 7 8 8 1 4 4 7 8 8 1 4 8 8 8 1 8 8 8 8 8 8 8 8 8 8 8 8	12.22 18.16 5.00 5.00 7.00 17.01 13.67 11.11 18.23 18.22 18.16 6.00 5.00 23.04 25.04 17.01 13.67 11.11 18.23 18.16 6.26 5.00 23.04 17.01 18.16 6.26 5.00 23.04 25.04 35 staff 17.01 18.23 12.22 18.16 6.26 6.00 23.04 25.04 35 staff 17.01 11.11 18.23 18.20 19.20	182 86 50 230 250 137 1111 182 122 182 86 50 230 230 137 1111 182 24 122 122 123 124 137 137 141 141 142 143 143 143 143 143 143 143 143 143 143	98 98 98 98 98 99 40 40 40 40 50 50 50 50 50 50 50 50 50 50 50 50 50	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	B (north)	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0			0	0	Access D Peak Tur Access B AM PM Access C AM Access C AM Access C AM	Dir IN O O Dir IN IN O O O O O O O O O O O O O O O O O	0 12467 18511 Split 100% 0 B 0 B 0 B Split 2/27 0 N 0 S 0 S	at each	eds Trunk Collecte h Access Split 100% 0 E 0 E Split 2/27 0 N 0 S 0 N 0 S Split 27W/33S	Peak Ford AM 2422 172 414 414 414 414 414 414 414 414 414 41	Road EB WB Σ INB SB Σ	(2010 x PM	1.16) EB WB Σ (2003 x 1.2) NB S S	PM) AM PM	Q _L 0	Q _R 0 Q _R 0 0 0	Qr1 147 Qr1 Qr1 269 242	Q ₁₂ ' 187 ' 187 ' Q ₁₂ ' Q ₁₃ ' Q ₁₄ ' Q ₁₅ ' Q ₁₆ ' Q ₁₇ ' Q	Q _M 187	Treatmei Nil Treatmei Nil Nil
77 88 1 2 3 4 5 9 10 6 7 8 1 1 2 2 mvale 1 5 9 10 6 7 7 8 1 1 2 mvale 1 1 3 4 4 5 9 1 0 6 7 7 8 8 1 1 2 1 1 2 1 1 1 1 2 1 1 1 1 1 1 1	12.22 18.16 5.00 17.01 13.67 11.11 18.23 12.22 18.16 600 stud 600	182 86 50 230 170 137 111 182 122 122 123 182 230 230 230 111 111 182 230 250 250 250 250 250 250 250 250 250 25	98 98 98 98 98 98 98 98 98 98 98 98 98 9	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	\$ [a (north) \$ [a (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0			0	0	Access D Peak Tur Access B AM PM Access C AM PM Access C AM	Dir IN O O O O O O O O O O O O O O O O O O	0 12467 18511 10006 0 B 0 B 0 B 0 B 0 B 0 B 0 B 0 B 0 B	Exce Dir OUT OUT OUT OUT OUT OUT OUT OUT	Access Split 100% 0 E 0 E Split 2/27 0 N 0 S 0 N 0 S 5plit 272W/33S 560 S	Peak Ford AM 242 1772 414 414 414 414 414 414 414 414 414 41	Road EB WB Σ INB SB SB SC ey Ro	(2010 x PM 147 147 147 147 147 147 147 147 147 147	1.16) EB WB Σ (2003 x 1.2) NB S Σ	PM) AM PM	Q _L 0	Q _R 0 Q _R 0 0 0	Qr1 147 Qr1 Qr1 269 242	Q ₁₂ ' 187 ' 187 ' Q ₁₂ ' Q ₁₃ ' Q ₁₄ ' Q ₁₅ ' Q ₁₆ ' Q ₁₇ ' Q	Q _M 187	Treatmei Nil Treatmei Nil Nil
77 88 1 2 33 44 59 90 100 66 77 81 59 90 100 60 77 81 11 2 mvale 1 1 2 mvale 1 1 3 4 4 5 9 10 4 5 9 10 4 5 9 10 4 5 9 10 4 5 9 10 4 5 9 10 10 10 10 10 10 10 10 10 10 10 10 10	12.22 18.16 5.00 23.04 17.01 13.67 11.11 18.23 18.16 5.00 23.04 25.04 26.05 26.05 27.06 27.07 28.16 29.07 29	182 86 6 50 230 250 250 250 250 250 250 250 250 250 25	98 145 645 645 645 645 645 645 645 645 645 6	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	B (north)	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0		0	0	000000000000000000000000000000000000000	Access D Peak Tur Access B AM PM Access C AM PM Access C AM Access D	0 1272 Dir IN 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	12467 18511 100% 100% 150% 150% 150% 160%	Dir OUT V OU	Split 100% 0 S O S O S O S O S O S O S O S O S O S	Peak AM 242 414 414 414 414 414 414 414 414 414	Road EB WB S NB SB SB NB SB SB SB	(2010 x PM 147 187 187 187 187 187 187 187 187 187 18	1.16) EB WB Σ (2003 x 1.2) NB SB J S SB J SB J SB J SB SB J SB SB J SB	PM AM PM AM	OL 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Q _R 0 Q _R 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Qr1 147 Qr1 Qr1 Qr1 Qr2	Qr2 187 Qr2 Qr2 Qr2 271 Qr2 271 Qr2	Q _M 187	Treatmet Treatmet Treatmet Signals on
7 8 8 1 2 3 3 4 4 5 9 10 6 6 7 8 8 1 1 2 2 mvale 1 1 2 2 mvale 1 1 2 2 mvale 1 1 2 2 5 7 8 8 1 1 2 2 5 7 8 9 9 10 6 6 7 7 8 8 1 1 2 2 5 7 8 1 1 2 2 5 7 8 1 1 2 2 5 7 8 1 1 1 2 2 5 7 8 1 1 1 2 2 5 7 8 1 1 1 2 2 5 7 8 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	12.22 18.16 5.00 23.04 17.01 13.67 11.11 18.23 18.16 5.00 23.04 25.04 26.05 26.05 27.06 27.07 28.16 29.07 29	182 86 50 1170 1271 182 182 122 122 182 1271 182 1271 182 1271 182 1271 182 1271 182 1271 1871 18	98 98 98 99 99 99 99 99 99 99 99 99 99 9	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	is B (north) B (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0	0	0	0	000000000000000000000000000000000000000	Access D Peak Tur Access B AM PM Access C AM Access C AM Access C AM	Dir IN O O Dir IN IN O O O O O O O O O O O O O O O O O	12467 18511 100% 100% 150% 150% 150% 160%	Dir OUT N O O O O O O O O O O O O O O O O O O	eds Trunk Collecte 1 Access Split 100% 0 E 0 E 0 E Split 2/27 0 N 0 S 0 N 0 S 50 N 0 S 500 S 458 W	Peak Ford AM 242 172 4144 Grah AM 226 494 Verm AM 202	Road EB WB S NB SB SB NB SB SB SB	(2010 x PM 147 147 147 147 147 147 147 147 147 147	1.16) EB WB Σ (2003 x 1.2) NB SB J S SB S	PM AM PM	OL 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Q _R 0 Q _R 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Qr1 147 Qr1 Qr1 Qr1 Qr2	Qr2 187 Qr2 Qr2 Qr2 271 Qr2 271 Qr2	Q _M 187	Treatmer Treatmer Treatmer Signals or
77 88 11 2 33 44 59 100 66 78 81 12 80 100 67 81 11 22 mvale 11 20	12.22 18.16 5.00 23.04 17.01 13.67 11.11 18.23 18.16 5.00 23.04 25.04 26.05 26.05 27.06 27.07 28.16 29.07 29.07 29.07 29.07 29.07 20	182 86 6 50 230 250 250 250 250 250 250 250 250 250 25	98 145 645 645 645 645 645 645 645 645 645 6	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	is B (north) B (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0	0	0	0	000000000000000000000000000000000000000	Access D Peak Tur Access B AM PM Access C AM PM Access C AM Access D	0 1272 Dir IN 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0	Dir OUT OUT OUT OUT OUT OUT OUT OUT	Split 12/2/7 O N O S O S Split 2/2/7 O N O S O S S S S S S S S S S S S S S S	Peak AM 242 414 414 414 414 414 414 414 414 414	Road EB WB S NB SB SB NB SB SB SB	(2010 x PM 147 187 187 187 187 187 187 187 187 187 18	1.16) EB WB Σ (2003 x 1.2) NB SB J S SB S	PM AM PM AM	OL 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Q _R 0 Q _R 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Qr1 147 Qr1 Qr1 Qr1 Qr2	Qr2 187 Qr2 Qr2 Qr2 271 Qr2 271 Qr2	Q _M 187	Treatmer Treatmer Nii Treatmer Signals or
77 88 11 2 33 44 59 100 66 78 81 12 80 100 67 81 11 22 mvale 11 20	12.22 18.16 5.00 23.04 17.01 13.67 11.11 18.23 18.16 5.00 23.04 25.04 26.05 26.05 27.06 27.07 28.16 29.07 29.07 29.07 29.07 29.07 20	182 86 6 50 230 250 250 250 250 250 250 250 250 250 25	98 145 645 645 645 645 645 645 645 645 645 6	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	is B (north) B (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0	0	0	0	000000000000000000000000000000000000000	Access D Peak Tur Access B AM PM Access C AM PM Access C AM Access D	Dir IN 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Split 2/27 ON OS Split 277W/33 140.5 Split 277W/33 140.5 Split 277W/33 140.5 Split 279W/33 150.5 Split 279W/33 Split 350.5	Dir OUT I OU	Split 100% 0 S Split 277W 560 S 458 W 0 N 210 S 172 W 0 N Split 100 S Split 270 S Split 270 S Split 270 S Split 270 S S S S S S S S S S S S S S S S S S S	Peak AM 242 414 414 414 414 414 414 414 414 414	Road EB WB S NB SB SB NB SB SB SB	(2010 x PM 147 187 187 187 187 187 187 187 187 187 18	1.16) EB WB Σ (2003 x 1.2) NB SB J S SB S	PM AM PM AM	OL 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Q _R 0 Q _R 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Qr1 147 Qr1 Qr1 Qr1 Qr2	Qr2 187 Qr2 Qr2 Qr2 271 Qr2 271 Qr2	Q _M 187	Treatmen Nil Treatmen Nil Nil
77 88 11 2 33 44 59 100 66 78 81 12 80 100 67 81 11 22 mvale 11 20	12.22 18.16 5.00 23.04 17.01 13.67 11.11 18.23 18.16 5.00 23.04 25.04 26.05 26.05 27.06 27.07 28.16 29.07 29.07 29.07 29.07 29.07 20	182 86 6 50 230 250 250 250 250 250 250 250 250 250 25	98 145 645 645 645 645 645 645 645 645 645 6	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	is B (north) B (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0	0	0	0	000000000000000000000000000000000000000	Access D Peak Tur Access B AM PM Access C AM ACCESS D	Dir IN 0 0 Dir IN 0 0 Dir IN 1 IN 254 891 Dir IN	Split 277/33 1405 Split 277/33	Dir OUT	Split 2/2/7 O N O S O S S S S W O N S S S S W O N S S S S S S S S S S S S S S S S S S	Peak AM 242 414 414 414 414 414 414 414 414 414	Road EB WB S NB SB SB NB SB SB SB	(2010 x PM 147 187 187 187 187 187 187 187 187 187 18	1.16) EB WB Σ (2003 x 1.2) NB SB J S SB S	PM AM PM AM	OL 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Q _R 0 Q _R 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Qr1 147 Qr1 Qr1 Qr1 Qr2	Qr2 187 Qr2 Qr2 Qr2 271 Qr2 271 Qr2	Q _M 187	Treatmen Nil Treatmen Nil Treatmen Signals or
77 88 11 2 33 44 59 100 66 78 81 12 80 100 67 81 11 22 mvale 11 20	12.22 18.16 5.00 23.04 17.01 13.67 11.11 18.23 18.16 5.00 23.04 25.04 26.05 26.05 27.06 27.07 28.16 29.07 29.07 29.07 29.07 29.07 20	182 86 6 50 230 250 250 250 250 250 250 250 250 250 25	98 145 645 645 645 645 645 645 645 645 645 6	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	is B (north) B (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0	0	0	0	000000000000000000000000000000000000000	Peak Tur Access B AM PM Access C AM Access C AM PM Access D AM PM	Dir IN 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Split 100% O B O S Split 140 O S O S Split 15 S O S O S S S S S S S S S S S S S S S	Dir	Split 10% O S Split 12727 O N O S Split 1272 W O N Split 1255/15N Split 1255/15N Split 150 O W O N O N Split 150 O W O N O N Split 150 O W O N O N O N Split 150 O W O N O N O N O N Split 150 O W O N O N O N O N Split 150 O W O N O N O N O N O N O N O N O N O N	Peak AM 242 414 414 414 414 414 414 414 414 414	Road EB WB S NB SB SB NB SB SB SB	(2010 x PM 147 187 187 187 187 187 187 187 187 187 18	1.16) EB WB Σ (2003 x 1.2) NB SB J S SB S	PM AM PM AM	OL 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Q _R 0 Q _R 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Qr1 147 Qr1 Qr1 Qr1 Qr2	Qr2 187 Qr2 Qr2 Qr2 271 Qr2 271 Qr2	Q _M 187	Treatmen Nil Treatmen Nil Nil
7 8 8 1 2 3 3 4 4 5 9 10 6 6 7 8 8 1 1 2 2 mvale 1 1 2 2 mvale 1 1 2 2 mvale 1 1 2 2 5 7 8 8 1 1 2 2 5 7 8 9 9 10 6 6 7 7 8 8 1 1 2 2 5 7 8 1 1 2 2 5 7 8 1 1 2 2 5 7 8 1 1 1 2 2 5 7 8 1 1 1 2 2 5 7 8 1 1 1 2 2 5 7 8 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	12.22 18.16 5.00 23.04 17.01 13.67 11.11 18.23 18.16 5.00 23.04 25.04 26.05 26.05 27.06 27.07 28.16 29.07 29.07 29.07 29.07 29.07 20	182 86 6 50 230 250 250 250 250 250 250 250 250 250 25	98 145 645 645 645 645 645 645 645 645 645 6	0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0% 0	is B (north) B (0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 0	0	0	0	000000000000000000000000000000000000000	Access D Peak Tur Access B AM PM Access C AM ACCESS D	Dir IN 0 0 Dir IN 0 0 Dir IN 1 IN 254 891 Dir IN	Split 100% Split 277W/33 140 S Split 277W/33 140 S Split 275W/33 Split 255/15M Split	Dir	eds Trunk Collecte 1 Access Split 100% 0 E 0 E 0 E Split 2/27 0 N 0 S 0 N 0 S 10 N 0 S 550 S 458 W 0 N 210 S 172 W 0 N 5plit 172 W 172 W 173 N 174 N 175 N 175 N 175 N 175 N 175 N 176 N 177 N 17	Peak AM 242 414 414 414 414 414 414 414 414 414	Road EB WB S NB SB SB NB SB SB SB	(2010 x PM 147 187 187 187 187 187 187 187 187 187 18	1.16) EB WB Σ (2003 x 1.2) NB SB J S SB S	PM AM PM AM	OL 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Q _R 0 Q _R 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	Qr1 147 Qr1 Qr1 Qr1 Qr2	Qr2 187 Qr2 Qr2 Qr2 271 Qr2 271 Qr2	Q _M 187	Treatmen


170769: Shepparton NEGC TIAR Addendum B Final Rev 2: 13/07/2018



ATTACHMENT E - POST-EXHIBITION CROSS-SECTIONS

170769: Shepparton NEGC TIAR Addendum B






NOTES:

- . Minimum street tree mature height 12 metres
- · All keirbs are to be SM modified (refer to the infrastructure Design Manual)

Section 1 Access Street (16.0m)








NOTES:

- . Minimum street tree mature height 12 metres.
- . All kerbs are to be 82 Barrier Kerb (fronting school or reserve SM Modified elsewhere)


Section 3 Reserve and School interface street (17.0m)












- + Minimum street tree mature height 15 metres.
- All kerbs are to be 60 Somer Kerb as per the infrastructure Design Manual.
- Where roads abut school drop-off zones and thoroughfores, grassed nature strip should be replaced with povernent. Canopy tree planting must be incorporated into any additional povernent.
- . Verge widths may be reduced where made abut open space with the consent of the responsible authority.

Section 6 Connector Street Level 1 (24.0m)







NOTES:

- . Minimum street tree moture height '5 metres.
- Allow by are to be \$2 Samer Kerbas per the Intrastructure Design Manual.
- Where roads abut its hoolidrap-off inches and thoroughteres, grave a nature-tinip should be replaced with povement. Concept tree planting must be incorporated into any additional povement.
- Verge widths may be reduced where roads abut open space with the consent of the responsible authority.

Section 7 Connector Street Level 2 (30.0m)



170769: Shepparton NEGC TIAR Addendum B

Final Rev 2: 13/07/2018



ATTACHMENT F - ROAD LENGTH COST ESTIMATES

Figure F1: Stand-alone development cross-section (Interim 1) for Road-01

					-
Description	Quantity	Unit	Rate \$	Amount	Comments
WORKS					
SITEWORKS AND EARTHWORKS					
Site preparation		Item			
Earthworks	1920	m³	30	57,600	16m wide x 0.3m deep x 400m
Other (Description)		Item			
ROAD PAVEMENT					
New Pavement	2920	m²	65	189,800	7.3m x 400m (urban pavement
Pavement Other		m²			
CONCRETE WORKS					
Kerb & Channel	800	Lm	48	38,400	400m x 2 sides
Pedestrian Paths	1200	m²	70	84,000	400m x 1.5m x 2 sides
DRAINAGE					
Drainage - pipes	22	Lm	152	3,344	3 x 300Ø cross culverts
	200	Lm	175	35,000	Adopt 375Ø half length
Drainage - pipes	200	Lm	210		Adopt 450Ø half length
			2200		2 @ 150m spacing
			17.5		400m x 2 sides
		Item			
Traffic signals		Item			
	32	No	150	4.800	25m spacing x 2 sides
					6m x 400m @ \$6/m²
		-			
		Item		150,000	
`				200,000	
		Item		8 000	
					
					
				1,500	
		iteiii			
		Itom			
		пеш	ć	650 144	
			3	055,144	
	2.25	0/_		21 /22	
VicRoads Fees	B	%		21,422	
	ţ	%		22.057	
Traffic Management	<u> </u>	(32,957	
		1/0		3,296	
Environmental Management	0.5	f		22.055	
Environmental Management Survey/Design	5	%		32,957	
Environmental Management Survey/Design Supervisio & Project Management	5 9	% %		59,323	
Environmental Management Survey/Design Supervisio & Project Management Site Establishment	5 9 2.5	% % %		59,323 16,479	
Environmental Management Survey/Design Supervisio & Project Management	5 9	% % %	\$	59,323	
	WORKS SITEWORKS AND EARTHWORKS Site preparation Earthworks Other (Description) ROAD PAVEMENT New Pavement Pavement Other CONCRETE WORKS Kerb & Channel Pedestrian Paths DRAINAGE Drainage - pipes Drainage - pipes Drainage - pipes Drainage - piss Drainage - miscellaneous TRAFFIC Traffic signals Traffic safety LANDSCAPE Trees Landscaping STREET LIGHTING Street lighting MISCELLANEOUS Line marking Regulatory signs Work maintenance - up to 1 year Landscape maintenance fee OTHER List SUB-TOTAL WORKS DELIVERY Council Fees	SITEWORKS AND EARTHWORKS Site preparation Earthworks 1920 Other (Description) ROAD PAVEMENT New Pavement 2920 Pavement Other CONCRETE WORKS Kerb & Channel 800 Pedestrian Paths 1200 DRAINAGE Drainage - pipes 200 Drainage - pipes 200 Drainage - pipes 800 Drainage - pites 60 Drainage - pites 60 Drainage - miscellaneous TRAFFIC Traffic signals Traffic safety LANDSCAPE Trees 32 Landscaping STREET LIGHTING Street lighting MISCELLANEOUS Line marking Regulatory signs Work maintenance - up to 1 year Landscape maintenance - 1yr/2 summers Traffic signals - 10 year maintenance fee OTHER List SUB-TOTAL WORKS DELIVERY	SITEWORKS AND EARTHWORKS Site preparation Item Earthworks 1920 m³ Other (Description) Item ROAD PAVEMENT	SITEWORKS AND EARTHWORKS Site preparation Item Earthworks 1920 m³ 30 Other (Description) Item ROAD PAVEMENT	SITEWORKS AND EARTHWORKS Item

170769: Shepparton NEGC TIAR Addendum B

Final Rev 2: 13/07/2018



Figure F2: Integrated development cross-section (Interim 2) for Road-01

	ROAD/INTERSECTION - COST EST	IIVIATEF	OK:	ROAD-01 Connector Street (24.0m) + Trunk termi				
Item	Description	Quantity	Unit	Rate \$	Amount	Comments		
	WORKS							
1	SITEWORKS AND EARTHWORKS							
1.1	Site preparation		Item					
	Earthworks	3000	m³	30	90,000	24m wide x 0.3m x 400m + 5%		
1.3	Other (Description)		Item		,			
	ROAD PAVEMENT							
	New Pavement	4650	m²	65	302,250	11.6m x 400m (urban pavemer		
	Pavement Other		m²			(company		
3	CONCRETE WORKS							
	Kerb & Channel	1000	Lm	48	48.000	400m x 2 sides + 200m (mediar		
	Pedestrian Paths	2000		35		400m x 2.5m x 2 sides		
	DRAINAGE				7 0,000			
	Drainage - pipes	36	Lm	152	5.472	3 x 300Ø cross culverts		
	Drainage - pipes	200		175		Adopt 375Ø half length		
	Drainage - pipes	200	ļ	210	(Adopt 450Ø half length		
	Drainage - pits		No	2200	·	2 @ 150m spacing		
	Drainage - subsoil drainage	1000	-	17.5		400m x 2 sides + 200m (mediar		
	Drainage - miscellaneous	1000	Item	17.5	17,300	400111 X 2 sides + 200111 (Illedial		
	TRAFFIC		iteiii					
	Traffic signals		Item					
	Traffic safety LANDSCAPE		Item					
		26	No	150	F 400	25m specing v 2 sides I medier		
	Trees	30	No	150		25m spacing x 2 sides + mediar		
	Landscaping		Item		15,000	6m x 400m @ \$6/m²		
	STREET LIGHTING		l de a ma		150,000			
	Street lighting		Item		150,000			
	MISCELLANEOUS		14		0.000			
	Line marking	***************************************	Item	***************************************	8,000			
	Regulatory signs		Item		1,500			
	Work maintenance - up to 1 year		Item		1,000			
	Landscape maintenance - 1yr/2 summers		Item		1,500			
	Traffic signals - 10 year maintenance fee		Item					
	OTHER							
9.1	List		Item					
	SUB-TOTAL WORKS			\$	805,822			
	DELIVERY							
	Council Fees	3.25			26,189			
	VicRoads Fees		%					
	Traffic Management		%		40,291			
	Environmental Management	0.5			4,029			
	Survey/Design		%		40,291			
10.6	Supervisio & Project Management		%		72,524			
10.7	Site Establishment	2.5	%		20,146			
10.8	Contingency	15	%		120,873			
	SUB-TOTAL DELIVERY			\$	324,343			
11	TOTAL ESTIMATED COST			Ś	1,130,165			



Figure F3: Connector Level 1 cross-section as per PSP (Ultimate 1) for Road-01

	ROAD/INTERSECTION - COST EST	IMATE F	OR:	ROAD-01	Connector	Street (24.0m as per PSP)
Item	Description	Quantity	Unit	Rate \$	Amount	Comments
	WORKS					
1	SITEWORKS AND EARTHWORKS			***************************************	***************************************	
1.1	Site preparation		Item			
1.2	Earthworks	2880	m³	30	86,400	24m wide x 0.3m x 400m
1.3	Other (Description)		Item			
2	ROAD PAVEMENT					
2.1	New Pavement	4650	m²	65	302,250	11.6m x 400m (urban pavemen
2.2	Pavement Other		m²			
3	CONCRETE WORKS					
3.1	Kerb & Channel	800	Lm	48	38,400	400m x 2 sides
3.2	Pedestrian Paths	2000	m²	35		400m x 2.5m x 2 sides
	DRAINAGE					
4.1a	Drainage - pipes	36	Lm	152	5,472	3 x 300Ø cross culverts
	Drainage - pipes	ļ	Lm	175		Adopt 375Ø half length
	Drainage - pipes	200	Lm	210	-	Adopt 450Ø half length
	Drainage - pits		No	2200		2 @ 150m spacing
	Drainage - subsoil drainage	800	Lm	17.5		400m x 2 sides
	Drainage - miscellaneous		Item		,,,,,	
	TRAFFIC					
5.1	Traffic signals		Item			
	Traffic safety		Item			
	LANDSCAPE					
6.1	Trees	32	No	150	4.800	25m spacing x 2 sides
	Landscaping		Item			6m x 400m @ \$6/m²
	STREET LIGHTING					
7.1	Street lighting		Item		150,000	
	MISCELLANEOUS					
8.1	Line marking		Item		8,000	
	Regulatory signs		Item		1,500	
	Work maintenance - up to 1 year		Item		1,000	
	Landscape maintenance - 1yr/2 summers		Item		1,500	
	Traffic signals - 10 year maintenance fee		Item			
	OTHER					
	List		Item			
	SUB-TOTAL WORKS			\$	788,522	
10	DELIVERY			······		
	Council Fees	3.25	%		25,627	
	VicRoads Fees	-	%			
	Traffic Management	L	%		39,426	
	Environmental Management	0.5			3,943	
	Survey/Design		%		39,426	
	Supervisio & Project Management	<u> </u>	%		70,967	
	Site Establishment	2.5			19,713	
	Contingency		%		118,278	
_0.0	SUB-TOTAL DELIVERY	10	,,,	\$		
	TOTAL ESTIMATED COST				1,105,902	



Figure F4: Trunk Collector cross-section + roundabout as per PSP (Ultimate 2) for Road-01

	NOAD/INTERSECTION - COST EST	ROAD/INTERSECTION - COST ESTIMATE FOR:				NOAD-01 ITUIK COILECTOI (30.0111 as per PSP)				
ltem	Description	Quantity	Unit	Rate \$	Amount	Comments				
	WORKS									
1	SITEWORKS AND EARTHWORKS									
1.1	Site preparation		Item							
1.2	Earthworks	3600	m³	30	108,000	30m wide x 0.3m x 400m				
1.3	Other (Description)		Item							
	ROAD PAVEMENT									
2.1	New Pavement	9280	m²	65	603,200	11.6m x 2 x 400m (urban)				
2.2	Pavement Other	340	m²	65		roundabout pavement				
3	CONCRETE WORKS									
3.1	Kerb & Channel	1600	Lm	48	76,800	400m x 2 sides x 2 c'ways				
3.2	Kerb & Channel		Lm	66		roundabout kerb + subsoil drain				
3.3	Pedestrian Paths	2000	m²	35	70,000	400m x 2.5m x 2 sides				
	DRAINAGE									
1.1a	Drainage - pipes	53	Lm	152	8,056	3 x 300Ø cross culverts				
	Drainage - pipes	200	ļ	175		Adopt 375Ø half length				
	Drainage - pipes	200		210		Adopt 450Ø half length				
	Drainage - pits	6	No	2200		2 @ 150m spacing				
	Drainage - subsoil drainage	1600	Lm	17.5		400m x 2 sides x 2 c'ways				
=	Drainage - miscellaneous		Item			,				
	TRAFFIC									
5.1	Traffic signals		Item							
***************************************	Traffic safety		Item							
	LANDSCAPE									
6.1	Trees	32	No	150	4,800	25m spacing x 2 sides				
6.2	Landscaping		Item		ļ	6m + 6m median x 400m @ \$6/m				
	STREET LIGHTING									
7.1	Street lighting		Item		150,000					
	MISCELLANEOUS				,					
8.1	Line marking		Item		8,000					
	Regulatory signs		Item		1,500					
=	Work maintenance - up to 1 year		Item		1,000					
	Landscape maintenance - 1yr/2 summers		Item		1,500					
=	Traffic signals - 10 year maintenance fee		Item							
	OTHER									
9.1	List		Item							
	SUB-TOTAL WORKS			Ś	1,205,796					
10	DELIVERY			T						
	Council Fees	3.25	%		39,188					
	VicRoads Fees	 	%							
=	Traffic Management	·	%		60,290					
	Environmental Management	0.5			6,029					
=	Survey/Design		%		60,290					
***************************************	Supervisio & Project Management	ţ	%		108,522					
	Site Establishment	2.5	ļ		30,145					
	Contingency	15			180,869					
	SUB-TOTAL DELIVERY	13		\$	485,333					
11	TOTAL ESTIMATED COST				1,691,129					



Figure F5: Stand-alone development cross-section (Interim 1) for Road-02

ltem	Description	Quantity	Unit	Rate \$	Amount	Comments
	WORKS					
1	SITEWORKS AND EARTHWORKS					
1.1	Site preparation		Item			
	Earthworks	3170	m³	30	95,100	16m wide x 0.3m x 600m + 10%
1.3	Other (Description)		Item			
2	ROAD PAVEMENT					
2.1	New Pavement	4820	m²	65	313,300	7.3m x 600m + 10% (urban)
2.2	Pavement Other		m²			
3	CONCRETE WORKS					
3.1	Kerb & Channel	1200	Lm	48	57,600	600m x 2 sides
3.2	Pedestrian Paths	1800	m²	70	126,000	600m x 1.5m x 2 sides
4	DRAINAGE					
4.1a	Drainage - pipes	30	Lm	152	4,560	4 x 300Ø cross culverts
4.1b	Drainage - pipes	300	Lm	175	52,500	Adopt 375Ø half length
4.1c	Drainage - pipes	300	Lm	210	63,000	Adopt 450Ø half length
4.2	Drainage - pits	8	No	2200	17,600	2 @ 150m spacing
4.3	Drainage - subsoil drainage	1200	Lm	17.5	21,000	600m x 2 sides
4.4	Drainage - miscellaneous		Item			
5	TRAFFIC					
5.1	Traffic signals		Item			
	Traffic safety		Item			
6	LANDSCAPE					
6.1	Trees	48	No	150	7,200	25m spacing x 2 sides
6.2	Landscaping		Item		22,000	6m x 600m @ \$6/m²
	STREET LIGHTING					
7.1	Street lighting		Item		150,000	
	MISCELLANEOUS				·	
8.1	Line marking		Item		8,000	
	Regulatory signs		Item		1,500	
	Work maintenance - up to 1 year		Item		1,000	
	Landscape maintenance - 1yr/2 summers		Item		1,500	
	Traffic signals - 10 year maintenance fee		Item			
	OTHER					
	List		Item			
	SUB-TOTAL WORKS			\$	941,860	
10	DELIVERY					
	Council Fees	3.25	%		30,610	
	VicRoads Fees		%			
	Traffic Management	ţ	%		47,093	
	Environmental Management	0.5			4,709	
	Survey/Design	ţ	%		47,093	
	Supervisio & Project Management		%		84,767	
	Site Establishment	2.5	·		23,547	
	Contingency	ţ	%		141,279	
10.8	SUB-TOTAL DELIVERY	15	70	\$	§	



Figure F6: Integrated development cross-section (Interim 2) for Road-02

	ROAD/INTERSECTION - COST EST	IIVIAIEF	OK:	KOAD-UZ Trunk Collector (30.0m)				
Item	Description	Quantity	Unit	Rate \$	Amount	Comments		
	WORKS							
1	SITEWORKS AND EARTHWORKS							
	Site preparation		Item					
	Earthworks	5400	m³	30	162,000	30m wide x 0.3m deep x 600m		
1.3	Other (Description)		Item		,			
	ROAD PAVEMENT							
2.1	New Pavement	6960	m²	65	452,400	2 x 5.8m x 600m (urban)		
	Pavement Other		m²					
	CONCRETE WORKS							
	Kerb & Channel	2400	Im	48	115.200	600m x 2 sides x 2 c'ways		
	Pedestrian Paths	3000		70		600m x 2.5m x 2 sides		
	DRAINAGE	3000		70	210,000	Occini x Eisini x Esides		
	Drainage - pipes	70	Lm	152	10 640	4 x 300Ø cross culverts		
	Drainage - pipes		Lm	175		Adopt 375Ø half length		
	Drainage - pipes		Lm	210		Adopt 450Ø half length		
	Drainage - pits		No	2200		2 @ 150m spacing		
	Drainage - subsoil drainage	2400		17.5		600 x 2 sides x 2 c'ways		
	Drainage - miscellaneous	2400	Item	17.5	72,000	OOO X 2 SIGES X 2 C Ways		
	TRAFFIC		iteiii					
	Traffic signals		Item					
	Traffic safety							
	LANDSCAPE		Item					
		70	Na	150	10.000	25 m. amarina y 2 aidea y mardia		
	Trees	12	No	150		25m spacing x 2 sides + median		
	Landscaping		Item		48,250	2 x 3.7m + 6.0m x 600m @ \$6/n		
	STREET LIGHTING		14		450,000			
	Street lighting		Item		150,000			
	MISCELLANEOUS				42.000			
	Line marking		Item		12,000			
	Regulatory signs		Item		3,000			
	Work maintenance - up to 1 year		Item		1,000			
	Landscape maintenance - 1yr/2 summers		Item		1,500			
	Traffic signals - 10 year maintenance fee		Item					
	OTHER							
9.1	List		Item					
	SUB-TOTAL WORKS			\$	1,351,890			
	DELIVERY							
	Council Fees	3.25	******************************		43,936			
	VicRoads Fees	ł	%					
	Traffic Management	4	%		67,595			
	Environmental Management	0.5			6,759			
	Survey/Design	-	%		67,595			
	Supervisio & Project Management	1	%		121,670			
10.7	Site Establishment	2.5	%		33,797			
10.8	Contingency	15	%		202,784			
	SUB-TOTAL DELIVERY			\$	544,136			
11	TOTAL ESTIMATED COST			Ś	1,896,026			



Figure F7: Connector Level 1 cross-section as per PSP (Ultimate 1) for Road-02

	ROAD/INTERSECTION - COST EST	IIVIA I E FOR:		ROAD-02 Connector Level 1 (24.0m) as per PSP				
ltem	Description	Quantity	Unit	Rate \$	Amount	Comments		
	WORKS							
1	SITEWORKS AND EARTHWORKS							
1.1	Site preparation		Item					
1.2	Earthworks	4320	m³	30	129,600	24m wide x 0.3m deep x 600m		
1.3	Other (Description)		Item					
2	ROAD PAVEMENT							
2.1	New Pavement	6960	m²	65	452,400	11.6m x 600m (urban pavemer		
2.2	Pavement Other		m²					
3	CONCRETE WORKS							
3.1	Kerb & Channel	1200	Lm	48	57,600	600m x 2 sides		
3.2	Pedestrian Paths	3000	m²	70	210,000	600m x 2.5m x 2 sides		
4	DRAINAGE							
4.1a	Drainage - pipes	48	Lm	152	7,296	4 x 300Ø cross culverts		
4.1b	Drainage - pipes	300	Lm	175	52,500	Adopt 375Ø half length		
4.1c	Drainage - pipes	300	Lm	210	63,000	Adopt 450Ø half length		
	Drainage - pits	8	No	2200		2 @ 150m spacing		
	Drainage - subsoil drainage	1200	Lm	17.5	21,000	600 x 2 sides		
4.4	Drainage - miscellaneous		Item					
	TRAFFIC							
5.1	Traffic signals		Item					
	Traffic safety		Item					
	LANDSCAPE							
6.1	Trees	48	No	150	7,200	25m spacing x 2 sides		
	Landscaping		Item		(2 x 3.7m x 600m @ \$6/m²		
	STREET LIGHTING							
7.1	Street lighting		Item		150,000			
	MISCELLANEOUS							
	Line marking		Item		12,000			
	Regulatory signs		Item		3,000	·		
	Work maintenance - up to 1 year		Item		1,000			
	Landscape maintenance - 1yr/2 summers		Item		1,500			
	Traffic signals - 10 year maintenance fee		Item					
	OTHER							
	List		Item					
	SUB-TOTAL WORKS			Ś	1,212,296			
10	DELIVERY			<u> </u>	,,			
	Council Fees	3.25	%		39,400			
	VicRoads Fees		%		22,130			
	Traffic Management		%		60,615			
	Environmental Management	0.5			6,061			
	Survey/Design		%		60,615			
	Supervisio & Project Management		%		109,107			
	Site Establishment	2.5			30,307			
	Contingency		%		181,844			
10.0	SUB-TOTAL DELIVERY	13	70	\$				
44	TOTAL BELIVERY TOTAL ESTIMATED COST				1,700,245	P		



Figure F8: Trunk Collector cross-section + roundabout as per PSP (Ultimate 2) for Road-02

	ROAD/INTERSECTION - COST ESTIMATE FOR			The second secon					
Item	Description	Quantity	Unit	Rate \$	Amount	Comments			
	WORKS								
1	SITEWORKS AND EARTHWORKS								
1.1	Site preparation		Item						
1.2	Earthworks	5400	m³	30	162,000	30m wide x 0.3m deep x 600m			
1.3	Other (Description)		Item						
	ROAD PAVEMENT								
2.1	New Pavement	6960	m²	65	452,400	2 x 5.8m x 600m (urban)			
	Pavement Other	340	_	65		roundabout pavement			
	CONCRETE WORKS					разона разона на н			
	Kerb & Channel	2400	Im	48	115,200	600m x 2 sides x 2 c'ways			
	Kerb & Channel	 	Lm	66		roundabout kerb + subsoil drai			
	Pedestrian Paths	3000		70	ļ	600m x 2.5m x 2 sides			
	DRAINAGE	3000		70	210,000	Occini x 2.3iii x 2.3ides			
	Drainage - pipes	70	Lm	152	10.640	4 x 300Ø cross culverts			
		300		ļ	<u> </u>	Adopt 375Ø half length			
	Drainage - pipes			175					
4.1c	Drainage - pipes	ļ	Lm	210		Adopt 450Ø half length			
	Drainage - pits		No	2200	ļ	2 @ 150m spacing			
	Drainage - subsoil drainage	2400	-	17.5	42,000	600 x 2 sides x 2 c'ways			
	Drainage - miscellaneous		Item						
	TRAFFIC								
	Traffic signals		Item						
5.2	Traffic safety		Item						
6	LANDSCAPE								
6.1	Trees	72	No	150	10,800	25m spacing x 2 sides + mediar			
6.2	Landscaping		Item		48,250	2 x 3.7m + 6.0m x 600m @ \$6/n			
7	STREET LIGHTING								
7.1	Street lighting		Item		150,000				
8	MISCELLANEOUS								
8.1	Line marking		Item		12,000				
8.2	Regulatory signs		Item		3,000				
	Work maintenance - up to 1 year		Item		1,000				
	Landscape maintenance - 1yr/2 summers		Item		1,500				
	Traffic signals - 10 year maintenance fee		Item						
	OTHER								
	List		Item						
	SUB-TOTAL WORKS			Ś	1,376,630				
10	DELIVERY			7	_,_,_,				
	Council Fees	3.25	%		44,740				
	VicRoads Fees	(%		17,7-10				
	Traffic Management	<u> </u>	%		68,832				
	Environmental Management	0.5			6,883				
		(%						
	Survey/Design	-	_		68,832				
	Supervisio & Project Management	\leftarrow	%		123,897				
	Site Establishment	2.5			34,416				
10.8	Contingency	15	%		206,495				
	SUB-TOTAL DELIVERY			\$					
11	TOTAL ESTIMATED COST			\$	1,930,724				

170769: Shepparton NEGC TIAR Addendum B

Final Rev 2: 13/07/2018



Figure F9: Stand-alone development cross-section (Interim 1) for Road-03

	ROAD/INTERSECTION - COST EST	IMATE F	OR:	ROAD-03	ROAD-03 Access Street (16.0m)				
Item	Description	Quantity	Unit	Rate \$	Amount	Comments			
	WORKS								
1	SITEWORKS AND EARTHWORKS								
1.1	Site preparation		Item						
	Earthworks	1920	m³	30	57,600	16m wide x 0.3m deep x 400m			
1.3	Other (Description)		Item						
2	ROAD PAVEMENT								
2.1	New Pavement	2920	m²	65	189,800	7.3m x 400m (urban pavement			
2.2	Pavement Other		m²			·			
3	CONCRETE WORKS								
3.1	Kerb & Channel	800	Lm	48	38,400	400m x 2 sides			
3.2	Pedestrian Paths	1200	m²	70	84,000	400m x 1.5m x 2 sides			
4	DRAINAGE								
4.1a	Drainage - pipes	22	Lm	152	3,344	3 x 300Ø cross culverts			
	Drainage - pipes	200	Lm	175		Adopt 375Ø half length			
	Drainage - pipes	200	Lm	210	42,000	Adopt 450Ø half length			
4.2	Drainage - pits	6	No	2200	13,200	2 @ 150m spacing			
4.3	Drainage - subsoil drainage	800	Lm	17.5	14,000	400 x 2 sides			
	Drainage - miscellaneous		Item						
	TRAFFIC								
5.1	Traffic signals		Item						
5.2	Traffic safety		Item						
6	LANDSCAPE								
6.1	Trees	32	No	150	4,800	25m spacing x 2 sides			
6.2	Landscaping		Item		15,000	6m x 400m @ \$6/m²			
7	STREET LIGHTING								
7.1	Street lighting		Item		150,000				
8	MISCELLANEOUS								
8.1	Line marking		Item		8,000				
8.2	Regulatory signs		Item		1,500				
8.3	Work maintenance - up to 1 year		Item		1,000				
8.4	Landscape maintenance - 1yr/2 summers		Item		1,500				
	Traffic signals - 10 year maintenance fee		Item						
	OTHER								
9.1	List		Item						
	SUB-TOTAL WORKS			\$	659,144				
10	DELIVERY								
10.1	Council Fees	3.25	%		21,422				
10.2	VicRoads Fees	1	%						
10.3	Traffic Management	5	%		32,957				
	Environmental Management	0.5	%		3,296				
10.5	Survey/Design	5	%		32,957				
	Supervisio & Project Management	9	%		59,323				
	Site Establishment	2.5	%		16,479				
	Contingency	15			98,872				
	SUB-TOTAL DELIVERY			\$	265,305				
11	TOTAL ESTIMATED COST			\$	924,449				



Figure F10: Integrated development cross-section (Interim 2) for Road-03

Item	Description	Quantity	Unit	Rate \$	Amount	Comments
	WORKS					
1	SITEWORKS AND EARTHWORKS					
1.1	Site preparation		Item			
1.2	Earthworks	2880	m³	30	86,400	24m wide x 0.3m deep x 400m
1.3	Other (Description)		Item			
2	ROAD PAVEMENT					
2.1	New Pavement	4640	m²	65	301,600	11.6m x 400m (urban pavement
2.2	Pavement Other		m²			
3	CONCRETE WORKS					
3.1	Kerb & Channel	800	Lm	48	38,400	400m x 2 sides
3.2	Pedestrian Paths	2000	m²	35	70,000	400m x 2.5m x 2 sides
4	DRAINAGE					
4.1a	Drainage - pipes	35	Lm	152	5,320	3 x 300Ø cross culverts
	Drainage - pipes	200	Lm	175		Adopt 375Ø half length
	Drainage - pipes	200	Lm	210		Adopt 450Ø half length
4.2	Drainage - pits	6	No	2200		2 @ 150m spacing
	Drainage - subsoil drainage	800	Lm	17.5		400 x 2 sides
	Drainage - miscellaneous		Item		,	
	TRAFFIC					
	Traffic signals		Item			
	Traffic safety		Item			
	LANDSCAPE					
	Trees	32	No	150	4.800	25m spacing x 2 sides
	Landscaping		Item			7.4m x 400m @ \$6/m²
	STREET LIGHTING				,	
	Street lighting		Item		150,000	
	MISCELLANEOUS					
	Line marking		Item		8,000	
	Regulatory signs		Item		1,500	
	Work maintenance - up to 1 year		Item		1,000	
	Landscape maintenance - 1yr/2 summers		Item		1,500	
	Traffic signals - 10 year maintenance fee		Item		1,500	
	OTHER		100111			
	List		Item			
J. 1	SUB-TOTAL WORKS		rcciii	\$	790,420	
10	DELIVERY			Y	750,420	
	Council Fees	3.25	%		25,689	
	VicRoads Fees	<u> </u>	%		23,003	
	Traffic Management	<u> </u>	%		39,521	
	Environmental Management	0.5			3,952	
	Survey/Design	<u> </u>	%		39,521	
		<u> </u>	%			
	Supervisio & Project Management	-{			71,138	
	Site Establishment	2.5			19,761	
10.8	Contingency	15	%		118,563	
	SUB-TOTAL DELIVERY			\$	318,144	



Figure F11: Connector Level 1 cross-section as per PSP (Ultimate 1) for Road-03

	ROAD/INTERSECTION - COST EST	IMATE F	OR:	ROAD-03	ROAD-03 Connector Street (24.0m) as per PSP				
ltem	Description	Quantity	Unit	Rate \$	Amount	Comments			
	WORKS								
1	SITEWORKS AND EARTHWORKS								
1.1	Site preparation		Item						
1.2	Earthworks	2880	m³	30	86,400	24m wide x 0.3m deep x 400m			
1.3	Other (Description)		Item		·				
	ROAD PAVEMENT								
2.1	New Pavement	4650	m²	65	302,250	11.6m x 400m (urban pavemen			
2.2	Pavement Other		m²			, ,			
3	CONCRETE WORKS								
3.1	Kerb & Channel	800	Lm	48	38,400	400m x 2 sides			
3.2	Pedestrian Paths	2000		35		400m x 2.5m x 2 sides			
	DRAINAGE								
	Drainage - pipes	36	Lm	152	5,472	3 x 300Ø cross culverts			
	Drainage - pipes	200	ļ	175		Adopt 375Ø half length			
	Drainage - pipes	200	 	210	<u> </u>	Adopt 450Ø half length			
	Drainage - pits		No	2200	č	2 @ 150m spacing			
	Drainage - subsoil drainage	800	ļ	17.5		400 x 2 sides			
	Drainage - miscellaneous	000	Item	17.5	11,000	loo x 2 states			
	TRAFFIC		reciii						
	Traffic signals		Item						
	Traffic safety		Item						
	LANDSCAPE		iteiii						
	Trees	22	No	150	4 900	25m spacing x 2 sides			
		32	1	150		6.0m x 400m @ \$6/m²			
	Landscaping STREET LIGHTING		Item		15,000	6.011 x 40011 @ \$6/111			
			lto m		150,000				
	Street lighting		Item		150,000				
	MISCELLANEOUS		14		0.000				
************	Line marking		Item		8,000				
	Regulatory signs		Item		1,500				
	Work maintenance - up to 1 year		Item	***************************************	1,000	}			
	Landscape maintenance - 1yr/2 summers		Item		1,500				
	Traffic signals - 10 year maintenance fee		Item	***************************************					
	OTHER								
9.1	List		Item						
	SUB-TOTAL WORKS		-	\$	788,522				
	DELIVERY								
	Council Fees	3.25	ļ		25,627				
	VicRoads Fees		%						
	Traffic Management		%		39,426				
	Environmental Management	0.5			3,943				
	Survey/Design	·	%		39,426				
	Supervisio & Project Management		%		70,967				
	Site Establishment	2.5			19,713				
10.8	Contingency	15	%		118,278				
	SUB-TOTAL DELIVERY			\$	317,380				
11	TOTAL ESTIMATED COST			\$	1,105,902				



Figure F12: Trunk Collector cross-section + roundabout as per PSP (Ultimate 2) for Road-03

	ROAD/INTERSECTION - COST ESTIMATE FOR:				ROAD-03 Trunk Collector (30.0m) as per PSP				
ltem	Description	Quantity	Unit	Rate \$	Amount	Comments			
	WORKS								
1	SITEWORKS AND EARTHWORKS								
1.1	Site preparation		Item						
1.2	Earthworks	3600	m³	30	108,000	30m wide x 0.3m deep x 400m			
1.3	Other (Description)		Item						
2	ROAD PAVEMENT								
2.1	New Pavement	9280	m²	65	603,200	11.6m x 2 x 400m (urban)			
2.2	Pavement Other	340	m²	65	22,100	roundabout pavement			
3	CONCRETE WORKS								
3.1	Kerb & Channel	1600	Lm	48	76,800	400m x 2 sides x 2 c'ways			
3.2	Kerb & Channel	40	Lm	66	2,640	roundabout kerb + subsoil drair			
3.3	Pedestrian Paths	2000	m²	35	70,000	400m x 2.5m x 2 sides			
4	DRAINAGE								
l.1a	Drainage - pipes	53	Lm	152	8,056	3 x 300Ø cross culverts			
1.1b	Drainage - pipes	200	Lm	175	35,000	Adopt 375Ø half length			
1.1c	Drainage - pipes	200	Lm	210	42,000	Adopt 450Ø half length			
4.2	Drainage - pits	6	No	2200	13,200	2 @ 150m spacing			
4.3	Drainage - subsoil drainage	1600	Lm	17.5	28,000	400 x 2 sides x 2 c'ways			
4.4	Drainage - miscellaneous		Item						
5	TRAFFIC								
5.1	Traffic signals		Item						
5.2	Traffic safety		Item						
6	LANDSCAPE								
6.1	Trees	32	No	150	4,800	25m spacing x 2 sides			
6.2	Landscaping		Item		30,000	6m + 6m median x 400m @ \$6/n			
7	STREET LIGHTING								
7.1	Street lighting		Item		150,000				
8	MISCELLANEOUS								
8.1	Line marking		Item		8,000				
8.2	Regulatory signs		Item		1,500				
8.3	Work maintenance - up to 1 year		Item		1,000				
8.4	Landscape maintenance - 1yr/2 summers		Item		1,500				
8.5	Traffic signals - 10 year maintenance fee		Item						
9	OTHER								
9.1	List		Item						
	SUB-TOTAL WORKS			\$	1,205,796				
10	DELIVERY								
10.1	Council Fees	3.25	%		39,188				
	VicRoads Fees		%						
10.3	Traffic Management	5	%		60,290				
	Environmental Management	0.5			6,029				
10.5	Survey/Design	5	%		60,290				
10.6	Supervisio & Project Management	9	%		108,522				
10.7	Site Establishment	2.5	%		30,145				
10.8	Contingency	15	%		180,869				
	SUB-TOTAL DELIVERY			\$	485,333				
11	TOTAL ESTIMATED COST				1,691,129				

